

AD-A156 009


NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS
SUCKER BROOK DAM (VT. (U) CORPS OF ENGINEERS WALTHAM MA
NEW ENGLAND DIV FEB 80


1/2

UNCLASSIFIED

F/G 13/13

NL





MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

PHOTOGRAPH THIS SHEET

AD-A156 009

DTIC ACCESSION NUMBER

II

LEVEL

1

INVENTORY

SUCKER BROOK DAM

DOCUMENT IDENTIFICATION

VT 00212

This document is approved for public release; its distribution is unlimited.

DISTRIBUTION STATEMENT

ACCESSION FOR

NTIS GRA&I

DTIC TAB

UNANNOUNCED

JUSTIFICATION



BY

DISTRIBUTION /


AVAILABILITY CODES

DIST

AVAIL AND/OR SPECIAL

A-1

DISTRIBUTION STAMP



DATE ACCESSIONED


DATE RETURNED

85 7 03 092

DATE RECEIVED IN DTIC

REGISTERED OR CERTIFIED NO.

PHOTOGRAPH THIS SHEET AND RETURN TO DTIC-DDAC



AD-A156 009

FINAL GEOTECHNICAL ENGINEERING
BRANCH

RICHELIEU RIVER BASIN
TOWN OF SALISBURY
ADDISON COUNTY, VERMONT

**SUCKER BROOK DAM
VT 00212**

**PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM**



DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
WALTHAM, MA 02154

FEBRUARY 1980

RECEIVED

SEP 4 1980

Geotech. Engrg. Br.

DISCLAIMER NOTICE

**THIS DOCUMENT IS BEST QUALITY
PRACTICABLE. THE COPY FURNISHED
TO DTIC CONTAINED A SIGNIFICANT
NUMBER OF PAGES WHICH DO NOT
REPRODUCE LEGIBLY.**

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER VT 00212	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Sucker Brook Dam NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS		5. TYPE OF REPORT & PERIOD COVERED INSPECTION REPORT
		6. PERFORMING ORG. REPORT NUMBER
7. AUTHOR(s) U.S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION		8. CONTRACT OR GRANT NUMBER(s)
9. PERFORMING ORGANIZATION NAME AND ADDRESS		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
11. CONTROLLING OFFICE NAME AND ADDRESS DEPT. OF THE ARMY, CORPS OF ENGINEERS NEW ENGLAND DIVISION, NEDED 424 TRAPELO ROAD, WALTHAM, MA. 02254		12. REPORT DATE February 1980
		13. NUMBER OF PAGES 120
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		15. SECURITY CLASS. (of this report) UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) DAMS, INSPECTION, DAM SAFETY, Richelieu River BasinTown of Salisbury Addison County, VT. Sucker Brook		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) The dam is an earth embankment with two angle points along its axis, about 660 ft. long and 36 ft. high. The dam is in fair condition. There were some significant conditions which should be corrected. The spillway is inadequate to pass the test flood. It is small in size with a significant hazard potential. The owner should implement various recommendations with in one year of receipt of the inspection report.		

RICHELIEU RIVER BASIN
TOWN OF SALISBURY
ADDISON COUNTY, VERMONT

**SUCKER BROOK DAM
VT 00212**

**PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM**

GORDON E. AINSWORTH & ASSOCIATES, INC.

Engineers, Surveyors and Planners

20 SUGARLOAF ST. SOUTH DEERFIELD, MASS. 01373



For use of this form, see AR 340-13, the proponent agency is TAGCEN.

SUBJECT

(c)

GEA

FROM

DATE _____

10 JUN 80

CMT 1

Chairman,
Dam Safety Review Board

Chief, Geotechnical Engrg. Branch

Chief, Water Control Br.

Attached for your review are two copies of the Architect-Engineer's draft report for
SUCKER BROOK Dam, Identity No. VT212.

The review board meeting date for this report is 23 JUN 80. Please present your comments in writing under the format shown below. Please return one copy with your comments. Cost code for this review is ABA06 0706 000000 (FY80)

Incl (dupe)
as

TERZIAN

6/13/80

NATIONAL PROGRAM OF INSPECTION OF NON-FEDERAL DAMS
DRAFT REPORT REVIEW COMMENTS

SUCKER BROOK DAM. IDENTITY NO. VT 00212

GEORGE ENG BRANCH

Page No.

Comments

S/S/F 1/11/1968
wt: 36'

NONE

GEOTECHNICAL ENGINEERING
BRANCH

RECEIVED

JUN 11 1957

Cocotech, Eners S.

NOTE: Bring nine (9) copies of comments to review board meeting.

LETTER OF TRANSMITTAL
FROM THE CORPS OF ENGINEERS TO THE STATE
TO BE SUPPLIED BY THE CORPS OF ENGINEERS

NATIONAL DAM INSPECTION PROGRAM

PHASE I INSPECTION REPORT

Identification No.: VT 00212
Name of Dam: Sucker Brook Dam
Town: Salisbury
County and State: Addison County, Vermont
Stream: Sucker Brook
Date of Inspection: 7 November 1979

BRIEF ASSESSMENT

1. Project Description

Sucker Brook Dam is an earth embankment, with two angle points along its axis, about 660 feet long by about 36 feet high. Included in the length of the dam is a 60-foot long spillway at the right abutment. Top width is about 10 feet, with an upstream slope of about 2.5H:1V and a downstream slope of about 2H:1V.

Normal pool elevation is maintained as much as 9 feet below the lower spillway crest by an outlet conduit starting from an intake structure and control tower, and running under the dam to a penstock at the downstream toe. The penstock carries all normal flow about 1.5 miles around a mountain to Silver Lake. The only spillway for the dam is a chute spillway at the right abutment, with two adjacent weir crests 4 feet different in elevation. The longer, lower weir crest is about 9 feet below the lowest point on the top of the dam.

2. Significant Findings and Assessment

The dam is in FAIR condition. Significant problems include several scarps near the upstream toeline about opposite the leftmost angle point of the dam; brush and small trees on the embankment slopes with some larger stumps on the downstream slope; cracking and undermining of the downstream end of the left concrete training wall of the spillway discharge channel; and what appears to be a significant amount of reservoir sedimentation that reduces total storage capacity and could hinder operation of the low level drain. Also, a hole was observed beneath the upstream extension of the left training wall of the original spillway (now covered with embankment) that could be a potential seepage path through the embankment.

3. Hydraulic and Hydrologic Findings

The spillway is INADEQUATE to pass the test flood without overtopping the dam. In accordance with recommended guidelines of the Corps of Engineers, the dam is classified as SMALL in size and as having a SIGNIFICANT hazard potential. Accordingly, a TEST FLOOD equal to ONE-HALF PMF (probable maximum flood) was judged as appropriate within the recommended range of the 100-year flood to one-half PMF. The test flood overtops the dam by a maximum of about 1.9 feet with duration of overtopping of about 5 hours. Peak inflow for the test flood is 7290 cfs. Peak outflow is unaffected by reservoir routing and is the same as peak inflow. Total project discharge capacity at the top of the dam is due to the two-level chute spillway plus the outlet penstock fully open, and is equal to 4280 cfs, or 59% of the test flood peak outflow.


4. Recommended Action

WITHIN ONE YEAR after their receipt of this Phase I Inspection Report, the Owner should implement the following recommendations:

- a. Engage a registered engineer qualified in the design of dams to do such work as: investigate the cause of the scarps near the upstream toeline; determine whether the hole that was observed beneath the upstream extension of the left training wall of the original spillway passes through the dam; advise how to repair or rebuild the downstream end of the left training wall of the spillway discharge channel which is cracked and undermined; and perform a detailed hydraulic and hydrologic study to better assess spillway capacity.
- b. Cut the brush and small trees from all slopes to a distance of about 20 feet downstream from the toeline.
- c. Verify the depth of sediment in the reservoir. Clean out all sediment at least down to the level of the low level drain.

Additional recommendations and remedial measures that should be implemented by the Owner WITHIN ONE YEAR after their receipt of this Phase I Inspection Report are described in Section 7.

GORDON E. AINSWORTH & ASSOCIATES, INC.


Kenneth J. Male, P.E.



This Phase I Inspection Report on _____ Dam has been reviewed by the undersigned Review Board members. In our opinion, the reported findings, conclusions, and recommendations are consistent with the Recommended Guidelines for Safety Inspection of Dams, and with good engineering judgment and practice, and is hereby submitted for approval.

THIS SHEET TO BE FURNISHED BY THE CORPS OF ENGINEERS

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation: however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external con-

limited to EL 1293 by intake opening, discharge capacity (limited by penstock) 100 cfs at top of dam @ EL 1311.2, 90 cfs at lower spillway crest @ EL 1302.

- b) Low Level Drain
24-inch diameter, discharge invert in outlet conduit EL 1284, intake invert EL 1284 but draft limited to EL 1288 by baffle weir in intake structure, discharge capacity included in outlet conduit and not estimated separately.
 - c) Outlet Conduit Drain Pipe
20-inch diameter, intake invert EL 1284 \pm , discharge invert unknown, discharge capacity not estimated.
- 2) Maximum Known Flood - unknown.
 - 3) Ungated spillway capacity at top of dam (2 weirs at different elevations), 4180 cfs @ EL 1311.2.
 - 4) Ungated spillway capacity at test flood pool, 5690 cfs @ EL 1313.1.
 - 5) Gated spillway capacity at normal pool - N/A.
 - 6) Gated spillway capacity at test flood pool - N/A.
 - 7) Total spillway capacity at test flood pool, 5690 cfs @ EL 1313.1.
 - 8) Total project discharge at top of dam, 4280 cfs @ EL 1311.2.
 - 9) Total project discharge at test flood pool, 7290 cfs @ EL 1313.1.

c. Elevation (feet - NGVD)

All elevations in this report are based on drawings by Nepsco Services, Inc., which are included in Appendix B3, and are assumed to be in approximate feet above mean sea level NGVD (National Geodetic Vertical Datum of 1929).

- | | | |
|----|--|------------|
| 1) | Natural Stream Bed at Toe of Dam - D/S | 1275 \pm |
| | - U/S | 1280 \pm |
| 2) | Bottom of Cutoff | None |
| a) | Lowest Foundation Surface | 1275 \pm |
| b) | Core Wall | None |

In September 1938 a flood caused severe damage to the spillway channel downstream of the dam necessitating its reconstruction. It was decided to relocate a new spillway founded on bedrock to the right of the old spillway. NEPSCO designed the new spillway, but the construction contractor for this work is unknown.

No other construction, modification, or major repair work is known to have occurred. Refer to Section 2 of this report for a complete discussion of the design, construction, and operation history.

i. Normal Operation Procedures

There are no known written operation and maintenance procedures for the dam. Maintenance personnel reportedly visit the dam weekly. Also, the Owner indicates that the dam is inspected annually by a private consultant. The water level in the reservoir presently is maintained as much as 9 feet below the spillway crest by the outlet conduit discharging into the penstock.

Refer to Section 4 of this report for a complete discussion of operation and maintenance procedures.

1.3 Pertinent Data

a. Drainage Area

- 1) Location - Central Vermont in northwestern foothills of Green Mountain National Forest.
- 2) River Basin - Sucker Brook to Lake Dunmore, then to Leicester River, to Otter Creek, to Lake Champlain, to Richelieu River.
- 3) Shape - Roughly square, 18,000 feet by 18,000 feet.
- 4) Area - 10.51 square miles, or 6726 acres.
- 5) Topography - Fairly steep wooded slopes averaging 5% to 20% slope. Elevations vary from EL 1293 to EL 3230.

b. Discharge at Dam Site (cfs)

1) Outlet Works

a) Outlet Conduit

3 feet-2 inches wide by 4 feet high through the dam followed by a 4-foot diameter penstock, discharge invert at penstock EL 1284, intake invert EL 1284 after gate well, but normal draft

e. Ownership

Since its construction, the dam has been and is still owned by:

Central Vermont Public Service Corporation (CVPS)
77 Grove Street
Rutland, Vermont 05701

Attention: Donald L. Rushford, Esq.
Vice President and General Counsel
(802) 773-2711

The dam and reservoir are located on Federally-owned land as part of the Green Mountain National Forest.

f. Operator

Day-to-day operation of the dam is the responsibility of:

J. Douglas Graham, Manager of Hydraulic Generation, CVPS
Edward Lurvey, General Hydraulic Foreman, CVPS

Both can be contacted at:

(802) 773-2711
(Same address as Owner)

g. Purpose of Dam

The dam diverts all the normal flow from Sucker and Dutton Brooks through a penstock to Silver Lake for later hydroelectric power generation as part of the Silver Lake Hydroelectric Development. (See Appendix D-1 and separate Phase I Inspection Report on Silver Lake Dam, VT 00196.) Water is not normally stored in Sucker Brook Reservoir. Major storage is provided upstream of the diversion dam on Sucker Brook by a much larger impoundment called Sugar Hill Reservoir. (See Appendix D-1 and separate Phase I Inspection Report on Sugar Hill Dam, VT 00176.)

h. Design and Construction History

The present Sucker Brook Dam was constructed in 1937 to replace an older concrete and rubble masonry dam at the same location, which had been in use for the same purpose for over 20 years. The present dam was designed by the New England Public Service Corporation (NEPSCO). Construction of the dam was performed by the Sanders Engineering Company under the direction of Frank H. Mason, NEPSCO Civil Engineer.

handwheel-operated rack gear mechanism exposed on top of the control tower. A rack structure and inclined intake opening on the upstream side of the control tower permit normal draft to about 9 feet below the lower spillway crest. A 24-inch diameter low level drain projecting upstream from the intake structure is limited to about 14 feet of draft below the lower spillway weir by a baffle weir in the intake structure. The invert of the low level drain and of the outlet conduit leaving the gate well is about 18 feet below the lower spillway crest.

The outlet conduit is a reinforced concrete box section 3 feet-2 inches wide by 4 feet high by about 100 feet long from the gate well through the dam to a 4-foot diameter penstock beginning just after the downstream toe. The foundation of the outlet conduit is reported to be rock at the upstream end and hard clay for the rest of its length. The penstock runs about 1.5 miles to Silver Lake. Connection to the penstock consists of a concrete transition to a round section, followed by a 47 3/4-inch diameter steel pipe section about 15 feet long with a 20-inch diameter drain pipe to the side, and then a short, partially-exposed corrugated metal pipe section to the penstock. The Owner indicates there are several such drain pipes from the penstock to the side along its route. The penstock was originally wood stave pipe, but it is thought to have been replaced in recent years with fully paved and coated, smooth-flow corrugated metal pipe.

c. Size Classification

In accordance with recommended guidelines (Reference 1), Sucker Brook Dam is classified as SMALL in size because its hydraulic height is 36 feet (within the 25 to 40-foot range) and its maximum storage capacity is 54 acre-feet (within the 50 to 1000 acre-foot range).

d. Hazard Classification

In accordance with recommended guidelines (References 1 & 18) involving loss of life and economic loss, Sucker Brook Dam is classified as having a SIGNIFICANT hazard potential. The dam itself is located in an isolated part of the Green Mountain National Forest and failure of the dam would cause little harm in this area. However, the increase in flow due to a dam failure would damage portions of Branbury State Park, increase damage to a highway bridge on Town Route 53 and to the road on either side of the bridge, and flood the first floors of about 8 houses along Lake Dunmore to a depth of less than 1 foot, with the moderate flow velocity of 7 fps probably damaging the homes. Total economic loss is judged appreciable. Loss of less than a few lives is judged possible. The dam failure analysis is developed in Section 5.5 of this report.

Access to the dam is from Town Route 53 to the west via a trail road up the mountain inside the Green Mountain National Forest (see Drainage Area Map, Appendix D-1).

The popular name of the dam is Sucker Brook Diversion Dam. The official name is Sucker Brook Dam. The popular and official name of the impoundment is Sucker Brook Reservoir. The reservoir is aligned along a northwest - southeast axis with the dam located at the northwest end.

The dam is built across Sucker Brook, which is tributary to Lake Dunmore. The nearest downstream community is named Lake Dunmore, population estimated at 50, located about 3 river miles downstream from the dam on the western side of Lake Dunmore, roughly opposite the mouth of Sucker Brook. The community of Lake Dunmore is not an incorporated village but simply a group of houses and other structures located in the Town of Salisbury.

b. Description of Dam and Appurtenances

Sucker Brook Dam is a rolled earth embankment of "well graded hardpan" with a rockfill downstream toe and a riprapped upstream slope. There are two angle points in the axis of the dam as it crosses a natural stream channel just downstream of the confluence of two brooks. The dam is about 660 feet long (including the spillway) by about 36 feet high. Top width is about 10 feet, with an upstream slope of about 2.5H:1V and a downstream slope of about 2H:1V.

No impervious core or zoning are known. Although called for, no cutoff is known. The foundation of the embankment is largely on "clay hardpan" with the left side near the outlet works reportedly on bedrock.

At the right abutment there is an ungated chute spillway with two adjacent concrete weir crests 4 feet different in elevation. The 40-foot long weir is about 9 feet below the low point on the top of dam and the 20-foot long weir is about 5 feet below the same point. The chute discharge channel runs down along the right abutment and joins the natural stream channel about 500 feet downstream of the dam. The approach channel, concrete weirs, and the discharge channel for some distance downstream of the weirs are founded on solid bedrock. The left side (toward the dam) of the approach channel, of the weir, and of the discharge channel through the dam section are lined with a vertical concrete training wall. The right side is the naturally sloped hillside.

Near the left end of the dam there is a concrete intake structure and control tower in the embankment near the upstream toe. Inside there is a 3-foot by 4-foot gate well with a 4-foot wide by 5-foot high service slide gate controlled by a

NATIONAL DAM INSPECTION PROGRAM

PHASE I INSPECTION REPORT

NAME OF DAM: SUCKER BROOK DAM, ID NO. VT. 00212

SECTION 1

PROJECT INFORMATION

1.1 General

a. Authority

The National Dam Inspection Act, Public Law 92-367, August 8, 1972, authorized the Secretary of the Army through the Corps of Engineers to initiate a national program of dam inspection throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England Region. Gordon E. Ainsworth and Associates, Inc. has been retained by the New England Division to inspect and report on selected dams in the State of Vermont. Authorization and notice to proceed was issued to Gordon E. Ainsworth and Associates, Inc., under a letter from William E. Hodgson, Jr., Colonel, Corps of Engineers. Contract No. DACW33-80-C-0012 has been assigned by the Corps of Engineers for this work.


b. Purpose of Inspection

- 1) Perform technical inspection and evaluation of non-Federal dams to identify conditions which threaten the public, and thus permit correction in a timely manner by non-Federal interests.
- 2) Encourage and assist the States to initiate quickly effective dam safety programs for non-Federal dams.
- 3) To update, verify, and complete the National Inventory of Dams.

1.2 Description of Project

a. Location

Referring to the Location and Vicinity Maps at the beginning of this report, Sucker Brook Dam is located in central Vermont in the Town of Salisbury, Addison County, about 3 miles east of the community of Salisbury. The dam at its maximum section is at Latitude 43 degrees - 54.1 minutes North, Longitude 73 degrees - 2.5 minutes West.



APPROX. SCALE IN MILES
0 2 4 8 12

DATUM - N.G.V.D. 1929, 100' CONTOUR INTERVAL

BASE MAP - 1:250,000 U.S.G.S. TOPO MAP

GLEN FALLS, N.Y., VT, N.H.,
1956, LIMITED REVISION 1967

IX



SUCKER BROOK DAM VICINITY MAP

GORDON E. AINSWORTH & ASSOCIATES INC.

Engineers, Surveyors, and Planners

20 SUGARLOAF ST. SOUTH DEERFIELD, MASS. 01373





SUCKER BROOK DAM LOCATION MAP


GORDON E AINSWORTH & ASSOCIATES INC.

Engineers, Surveyors and Planners



viii

20 SUGARLOAF ST. SOUTH DEERFIELD MASS 01373



Overview Photo - Sucker Brook Dam - 11/30/79

6 - EVALUATION OF STRUCTURAL STABILITY

6.1	Visual Observations	6-1
6.2	Design and Construction Data	6-1
6.3	Post-Construction Changes	6-2
6.4	Seismic Stability	6-2

7 - ASSESSMENT, RECOMMENDATIONS, AND REMEDIAL MEASURES

7.1	Dam Assessment	
a.	Condition	7-1
b.	Adequacy of Information	7-1
c.	Urgency	7-2
7.2	Recommendations	7-2
7.3	Remedial Measures	
a.	Operation and Maintenance Procedures	7-3
7.4	Alternatives	7-4

APPENDICES

APPENDIX A - INSPECTION CHECKLIST

APPENDIX B - ENGINEERING DATA

APPENDIX C - PHOTOGRAPHS

APPENDIX D - HYDRAULIC AND HYDROLOGIC COMPUTATIONS

APPENDIX E - INFORMATION AS CONTAINED IN THE NATIONAL INVENTORY
OF DAMS

APPENDIX F - REFERENCES

TABLES

Table 5.1	Overtopping Analysis	5-7
Table 5.2	Dam Failure Analysis	5-10

c.	Appurtenant Structures	
1)	Intake Structure and Control Tower	3-2
2)	Service Bridge	3-4
3)	Outlet Conduit	3-4
4)	Spillway and Discharge Channel	3-4
d.	Reservoir Area	3-5
e.	Downstream Channel	3-6
3.2	Evaluation	3-6
4 -	OPERATION AND MAINTENANCE PROCEDURES	
4.1	Operation Procedures	
a.	General	4-1
b.	Emergency Action Plan and Warning System	4-1
4.2	Maintenance Procedures	
a.	General	4-2
b.	Operating Facilities	4-2
4.3	Evaluation	4-2
5 -	EVALUATION OF HYDRAULICS AND HYDROLOGY	
5.1	General	5-1
5.2	Design Data	5-1
5.3	Experience Data	5-1
5.4	Test Flood Analysis	
a.	Initial Conditions	5-2
b.	Storage Capacity	5-2
c.	Discharge Capacity	5-3
d.	Selection of Test Flood	5-4
e.	Development of Test Flood	5-4
f.	Overtopping Potential	5-6
5.5	Dam Failure Analysis	
a.	Failure Conditions	5-6
b.	Results of Analysis	5-9
c.	Hazard Evaluation	5-9

1.3 Pertinent Data

a.	Drainage Area	1-5
b.	Discharge at Dam Site	1-5
c.	Elevation	1-6
d.	Reservoir	1-7
e.	Storage	1-7
f.	Reservoir Surface	1-7
g.	Dam	1-8
h.	Diversion and Regulating Tunnel	1-8
i.	Spillway	1-8
j.	Regulating Outlets	
	1) Low Level Drain	1-9
	2) Outlet Conduit	1-9
	3) Outlet Conduit Drain Pipe	1-10

2 - ENGINEERING DATA

2.1	Design Data	2-1
-----	-------------	-----

2.2 Construction Data

a.	Initial Construction	2-1
b.	Modifications	2-2
c.	Repairs and Maintenance	2-2
d.	Pending Remedial Work	2-2

2.3 Operation Data

a.	Inspections	2-3
b.	Performance Observations	2-3
c.	Water Levels and Discharges	2-3
d.	Past Floods	2-3
e.	Previous Failures	2-3

2.4 Evaluation

a.	Availability	2-3
b.	Adequacy	2-4
c.	Validity	2-4

3 - VISUAL INSPECTION

3.1 Findings

a.	General	3-1
b.	Dam	3-1

SUCKER BROOK DAM
PHASE I INSPECTION REPORT
TABLE OF CONTENTS

	<u>Page</u>
Letter of Transmittal	-
Brief Assessment	1
Review Board Page	-
Preface	i
Table of Contents	iii
Overview Photo	vii
Location Map	viii
Vicinity Map	ix
<u>Section</u>	
1 - PROJECT INFORMATION	
1.1 General	
a. Authority	1-1
b. Purpose of Inspection	1-1
1.2 Description of Project	
a. Location	1-1
b. Description of Dam and Appurtenances	1-2
c. Size Classification	1-3
d. Hazard Classification	1-3
e. Ownership	1-4
f. Operator	1-4
g. Purpose of Dam	1-4
h. Design and Construction History	1-4
i. Normal Operation Procedures	1-5

ditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions will be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aide in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

The Phase I Investigation does not include an assessment of the need for fences, gates, no-trespassing signs, repairs to existing fences and railings and other items which may be needed to minimize trespass and provide greater security for the facility and safety to the public. An evaluation of the project for compliance with OSHA rules and regulations is also excluded.

3)	Maximum Tailwater	Unknown
4)	Normal Pool (site inspection 11/7/79)	1293 \pm
5)	Full Flood Control Pool	N/A
6)	Spillway Crest (ungated chute spillway)	
	- lower weir	1302
	- upper weir	1306
7)	Design Surcharge	Unknown
8)	Top of Dam - low point	1311.2
	- high point	1312.3
	- design	1312
9)	Test Flood Surcharge	1313.1
d.	<u>Reservoir</u> (length in feet)	
1)	Normal Pool	300 \pm
2)	Flood Control Pool	N/A
3)	Spillway Crest Pool (lower weir)	500 \pm
4)	Top of Dam	700 \pm
5)	Test Flood Pool	800 \pm
e.	<u>Storage</u> (acre-feet)	
1)	Normal Pool	5
2)	Flood Control Pool	N/A
3)	Spillway Crest Pool (lower weir)	21
4)	Top of Dam	54
5)	Test Flood Pool	63
f.	<u>Reservoir Surface</u> (acres)	
1)	Normal Pool	1.1
2)	Flood Control Pool	N/A
3)	Spillway Crest Pool (lower weir)	3.0
4)	Top of Dam	4.5
5)	Test Flood Pool	5.0

g. Dam

- 1) Type - Earth.
- 2) Length - 660 feet including spillway.
- 3) Height - Hydraulic Height - 36 feet.
- Structural Height - 36 feet.
- 4) Top Width - About 10 feet.
- 5) Side Slopes - Upstream - About 2.5H:1V.
- Downstream - About 2H:1V.
 - a) Approximate Volume of Dam - 30,000 cubic yards.
- 6) Zoning - None known. Design called for pervious upstream and downstream shells. But description by Barrows during construction indicates dam is homogeneous "clay hardpan" with rockfill downstream toe and riprap upstream.
- 7) Impervious Core - See Zoning.
- 8) Cutoff - None known. Concrete cutoff was called for in locations where embankment was founded on rock.
- 9) Grout Curtain - None.
- 10) Other - Foundation of embankment is largely on "clay hardpan" and spillway is on bedrock. Left side of embankment rear outlet is on bedrock.

h. Diversion and Regulating Tunnel - N/A

i. Spillway

- 1) Type - Chute, with two adjacent concrete overflow weir control sections at different elevations, founded on rock.
- 2) Length of Weirs - lower weir - 40 feet.
- upper weir - 20 feet.
- 3) Crest Elevation - w/o flashboards
lower weir - 1302
upper weir - 1306
- w/ flashboards - N/A

- 4) Gates - None.
- 5) Upstream Channel - Natural bedrock-bottom approach section with reinforced concrete training wall on left side of control section and natural hillside on right.
- 6) Downstream Channel - About a 500-foot long chute, founded partly on rock, along right abutment with a natural bottom narrowing in width away from spillway. Left training wall is reinforced concrete along dam section, right side is natural hillside.
- 7) General - No comment.

j. Regulating Outlets

1) Low Level Drain

- a) Invert - Intake EL 1284, Discharge EL 1284. Baffle weir in intake structure permits draft only to EL 1288.
- b) Size - 24-inch diameter.
- c) Description - Steel pipe stub about 25 feet long from upstream toe of dam to intake structure, with the intake structure discharging through the gate well into outlet conduit under dam.
- d) Control Mechanism - None itself. Control provided by outlet conduit slide gate in gate well.
- e) Other - No comment.

2) Outlet Conduit

- a) Invert - Intake EL 1284 after gate well, Discharge EL 1284. Rack structure and intake opening just upstream of gate well permit normal draft to about EL 1293. Draft to EL 1288 by low level drain limited by baffle weir.
- b) Size - 3 feet-2 inches wide by 4 feet high.

c) Description - Reinforced concrete box section about 100 feet long from gate well through dam section. At downstream toe, there is a concrete transition section from rectangular box to a 47 3/4-inch diameter steel pipe section about 15 feet long. This steel pipe is then joined with a short, partially-exposed corrugated metal pipe section to a 4-foot diameter penstock about 1.5 miles long to Silver Lake. The penstock discharges at about EL 1270 into an open channel just short of Silver Lake. Penstock was originally wood stave pipe, but it is thought to have been replaced in recent years with fully paved and coated, smooth-flow corrugated metal pipe.

d) Control Mechanism - 4-foot wide x 5-foot high slide gate in the gate well at the upstream end, which is controlled by a handwheel-operated rack gear mechanism on top of the control tower directly above.

e) Other - No comment.

3) Outlet Conduit Drain Pipe

a) Invert - Intake EL 1284 \pm , Discharge invert unknown.

b) Size - 20-inch diameter.

c) Description - Steel pipe from bottom of 47 3/4-inch diameter steel pipe section (between outlet conduit and penstock) discharging into the stream channel downstream of the dam to the right of the penstock.

d) Control Mechanism - A normally-closed cover or bulkhead accessible through a manhole in the top of the 47 3/4-inch diameter steel pipe section.

e) Other - No comment.

SECTION 2

ENGINEERING DATA

2.1 Design Data

The present Sucker Brook Dam was designed in about 1937 for the current owner, Central Vermont Public Service Corporation (CVPS), by the New England Public Service Corporation (NEPSCO), to replace an older concrete and rubble masonry dam which had been in use for over 20 years. NEPSCO was thought to be the present New England Power Service Corporation, located at 25 Research Drive, Westborough, Massachusetts 01581, telephone (617) 366-9011. They were contacted, but they indicated that they could find no data on the dam. Subsequently, it was learned that they are not the successors to NEPSCO. The present business status and location of NEPSCO is unknown.

The only available data covering the design and construction of the dam is included in Appendix B3. It consists of copies of a letter (starting on Appendix B3-9) and a report (starting on Appendix B3-11) on construction. This material was prepared by H.K. Barrows, Consulting Engineer of Boston, in 1937 during and just after the completion of construction. A CVPS petition to the Vermont Public Service Commission for authority to construct the dam contains some additional data and is included starting on Appendix B3-1. Included with this petition were a drainage area map (see Appendix B3-5) as well as some design plans, sections, and details (see Appendices B3-6 through 8). The order approving the dam construction from the Vermont Public Service Commission is included as Appendix B3-18.

No other design data or drawings were available. The construction specifications were not available.

2.2 Construction Data

a. Initial Construction

Construction of the dam for CVPS was completed in 1937. The dam was constructed by the Sanders Engineering Company under the direction of Frank H. Mason, NEPSCO Civil Engineer. The resident engineer and superintendent are identified on Appendix B3-16. The present business status and location of Sanders Engineering is unknown.

Background data on the original construction is contained in the letter, report, and CVPS petition discussed in Section 2.1. The original construction included an embankment with a maximum reported height of approximately 40 feet at design top EL 1312, an embankment length of about 400 feet, a concrete spillway with a 150-foot long crest at EL 1306, and an outlet conduit through

the dam to a wood stave penstock. The old concrete and rubble masonry dam was left in place about 50 to 100 feet upstream of the embankment.

No other records on the original construction of the dam are known.

b. Modifications

In September 1938 a flood occurred which "caused the spillway channel below the dam to be so badly washed as to necessitate" reconstruction and relocation of the channel and the spillway. A letter by H.K. Barrows in November 1939 (see Appendix B3-19) describes the damage which occurred, the new design, and the construction of the spillway improvement.

The new spillway was designed by NEPSCO in 1939. Construction was completed by November 1939 under the direction of NEPSCO engineers. However, the construction contractor for this work is unclear. On Appendix B3-21, a "Mr. Merry" is identified as "Contractor", but it is not evident whether he was the actual contractor or just the superintendent.

The new spillway construction resulted in addition of a second bend point and lengthening of the embankment to its present total of about 600 feet. The new spillway consisted of two adjacent concrete weirs located to the right of the old spillway (now embankment), with crests 40 and 20 feet long at EL 1302 and EL 1306, respectively. The lower weir had 4-foot high pin-type flashboards when it was constructed originally, but they have been subsequently removed and their supports have been cut off at the weir crest. One design plan of the new spillway by NEPSCO was included with Barrows' Report of November 1939 and is included as Appendix B3-23.

The original wood stave penstock about 1.5 miles long to Silver Lake is thought to have been replaced in recent years with fully paved and coated, smooth-flow corrugated metal pipe.

No records of any other modifications to the dam are known.

c. Repairs and Maintenance

No records of any repairs to the dam are known.

d. Pending Remedial Work

The Owner has no plans for any pending remedial work.

2.3 Operation Data

a. Inspections

Only one inspection report was available and it is included starting on Appendix B3-24. The report was prepared by Stephen H. Haybrook, on behalf of the State of Vermont, on April 17, 1951. It contains some general data, a historical brief, and a description of the dam. It was stated in the report that the "dam appears in a good condition" but that "the discharge channel may be subjected to erosion in flood time but the safety of the dam from such a condition would not be affected." The report contains the concluding statement that "there is no appreciable change in the stability of this dam since its construction."

The Owner indicates that the dam is inspected annually by the firm of Kleinschmidt and Dutting, Engineering Consultants, 70 Main Street, Pittsfield, Maine 04967, telephone (207) 487-3328. However, the Owner did not make the results of those inspections available for review.

b. Performance Observations

There is no instrumentation in the dam. Other than observations made during the inspection previously discussed in Section 2.3.a, there are no other known performance observations.

c. Water Levels and Discharges

There are no known records of routine water levels and discharges from the dam.

d. Past Floods

Other than the brief account of the September 1938 flood in Barrows' report on spillway improvement (see Appendix B3-19), there are no other known records of past floods at the dam.

e. Previous Failures

There are no known previous failures of the dam.

2.4 Evaluation

a. Availability

As listed on Appendix B1, various engineering data and records are available in the files of the Dam Safety Engineer of the Vermont Department of Water Resources, of the Vermont Public

Service Board, and of Vermont Public Records. This data was reviewed, and copies of the records significant to the dam are included in chronological order in Appendix B3. Discussion of the data starts at the beginning of this section of the report. The Owner was unwilling to make their annual inspection reports or other data on file available. The Owner did make one drawing available for review during the field inspection, but the Owner would not allow it to be photographed and would not release it for subsequent review.

b. Adequacy

Available data consisted of a letter and two reports on construction of the dam and relocation and construction of the new spillway 2 years later, including poor copies of four various design/construction drawings, together with one report of an inspection some years later. Such data as the design calculations, construction specifications, detailed data on the foundation and embankment soils, and detailed operation and performance data were not available. The lack of such in-depth engineering data does not permit a comprehensive review. Therefore, the adequacy of this dam could not be assessed with respect to reviewing design, construction, and operation data.

c. Validity

Based on field observation and checking, the limited data available generally appears valid. Some exceptions noted are:

- 1) Original data in Appendix B3 indicate that the dam crest was intended to be at EL 1312, 10 feet higher than the lower spillway crest. Field measurements (see Appendix B2) show that the crest is non-level with the low point at EL 1311.2, 9.2 feet above the lower spillway crest. Also, original data indicate a maximum embankment height of 40 feet. From present analysis it appears that the structural height of the embankment is only about 36 feet to the actual low point of the dam crest, or about 37 feet to the design crest at EL 1312.
- 2) Existing engineering data indicate a total drainage area of 8.7 to 9.0 square miles and a drainage area tributary to Sugar Hill Reservoir of 2.3 to 2.5 square miles (see Appendices B3-3, B3-11, and B3-24). As discussed later in Section 5.1, present measurement yields about 10.51 square miles total (as much as about 21% more than reported) and 2.97 square miles to Sugar Hill Reservoir (as much as about 29% more than reported).

SECTION 3
VISUAL INSPECTION

3.1 Findings

a. General

Sucker Brook Dam was inspected on November 7, 1979. The inspection party (see Appendix A-1) was accompanied by two representatives of the Owner: Mr. J. Douglas Graham, Manager of Hydraulic Generation, and Mr. Edward Lurvey, General Hydraulic Foreman. Also present was Mr. Peter Barranco, Jr., Dam Safety Engineer of the Vermont Department of Water Resources. The weather was drizzly and overcast and the temperature was about 45° F. The water surface was very low at about EL 1293, about 9 feet below the lower spillway crest. The Visual Inspection Checklist is included as Appendix A, while selected photos taken during the inspection are included in Appendix C. Appendix C-1 is a photo index map. The Overview Photo at the beginning of the report as well as a couple of the photos in Appendix C are aerial photos taken from a helicopter on November 30, 1979.

b. Dam

In plan view this dam contains two bends, or angle points (see Overview Photo and Appendix C-1). At the rightmost angle point there exists a concrete wall which appears to pass entirely through the embankment transversely. Photo C-2A (extreme left center) shows the upstream end of the wall. The crest of the dam extends above the top of the wall about 3 to 4 feet. Photo C-2B is a detail of the upstream end which extends into the reservoir behind the dam. A large hole was found immediately to the right and underneath the upstream end of this wall. The hole is about 8-inch diameter and extends into the ground at least 2 feet. It is possible that this hole is the upstream end of a hole that passes through the dam along this wall. Inspection of the potential downstream exit points of any such hole revealed the presence of heavy riprap in those areas.

Inspection of the upstream end of this wall during periods of high water is indicated. It may be possible to observe small whirlpools above the hole if significant flow is occurring. Also, dye could be added above the hole to determine whether it moves downward into the hole.

On the downstream side of the dam about 30 feet left from the above-described wall and behind the vehicles shown in Photo C-3A, about 10 to 20 feet downstream from the apparent toe-line, three 6-inch diameter holes were found in the ground. These

appeared to be animal holes. One of these holes had numerous rocks in the bottom. It seems that topsoil had been placed over rockfill and that the topsoil had locally eroded into the larger openings. There was no reason to suspect that these holes were connected in any way with the upstream side of the dam.

Near the upstream toeline of the dam, opposite the person on the crest in Photo C-3B (near the left angle point in the dam), several small scarps have developed. The location of the scarps is also shown in Photo C-4A where the person in the orange raincoat is standing. These scarps are 6 to 18 inches high and extend for a longitudinal distance of about 15 feet. One scarp is about 3 feet downstream and another about 6 feet downstream from the toeline. The material in the reservoir bottom and in these scarps is highly organic. They appear to be localized slumps caused by placement of fill over peaty organic soil that seems to form part of the bottom of the reservoir.

The downstream slope of the dam is shown in Photos C-5A and C-5B, which overlap to display a continuous view of the slope. The slope is covered with brush about 6 feet in height, and stumps up to 8-inch diameter are found sporadically throughout. A few bare spots were found on the slope, but no significant erosion has occurred. On the downstream portion of the slope, up to about 15 feet above the downstream toeline, rock cover exists which now has been substantially overgrown. Some of the rock cover is seen at the lower left in Photo C-5A. Another view of the downstream slope, looking from right to left, is given in Photo C-4B. The rock cover is evident in most of the photo.

Riprap covers the entire upstream face. Some of the riprap is shown in Photo C-6B. In many locations the riprap is covered with loam and brush, and it is, therefore, difficult to see without close inspection. There was no way to judge whether a properly graded filter was placed beneath the riprap.

The original plans (1937) indicate that riprap was placed on the entire upstream face, but no mention was made of filter material. The hardpan in the embankment, against which the riprap was placed, was noted to be "well graded."

Leakage was observed exiting from the rock cover at the downstream toeline at a rate of about 4 gpm. The seepage was clear. The discharge channel and some ponded water downstream are shown in Photo C-6A.

c. Appurtenant Structures

1) Intake Structure and Control Tower

The intake structure and control tower are one and the same concrete structure located just upstream of the dam

near the left end (see Overview Photo). The actual intake is an inclined port just upstream of the control tower covered by a large wooden trash rack structure (see Photo C-7A). The inspection checklist for the intake is on Appendix A-4. The inspection checklist for the control tower is on Appendix A-5. Only the outside of the intake structure and control tower were inspected. The inside was not readily accessible and was also partially submerged. For similar reasons, the 24-inch diameter low level drain pipe projecting upstream from the bottom of the intake structure was not inspected. As discussed later in Section 3.1.d, the inlet to this low level drain may be buried by sediment.

From what was readily visible, the intake structure and wooden trash rack are in fair to good condition. As seen in Photo C-7A, leaves and trash had collected against the rack structure and were causing some flow obstruction. The low water level and the partially exposed reservoir bottom, that appears like a bog, aggravate this condition. The inclined steel trash rack shown directly over the intake by the design/construction drawings (see Appendix B3-8) was not noted during the inspection.

The outside of the concrete control tower is in good condition, except for deterioration at the support seat for the service bridge (see Photo C-8A) and for a vertical crack on the left side of the tower (see Photo C-8B). Deterioration on the right side of the support seat was about as advanced as that shown on the left side by Photo C-8A, except that the loose concrete had not fallen off yet. The vertical crack on the left side of the tower starts at a railing post socket on top and appeared to narrow toward the base. No leakage was observed, since the water level inside the tower was lower than the ground at the base of the tower.

On top of the control tower there is a handwheel-operated rack gear control mechanism (see Photo C-7B), which operates the service slide gate in the gate well directly underneath. The handwheel was secured with a padlocked chain and was not operated, but the entire mechanism appeared in serviceable condition. The service gate appeared to be fully open during the inspection.

The lower horizontal pipe railing on top of the control tower toward the intake was not secured on its left end. Welds are broken and a section of railing is missing at this point. (Just visible in Photo C-7A.)

2) Service Bridge

The service bridge is a wood-decked walkway supported on open web beams spanning about 20 feet from a point just upstream of the dam crest to a seat on the control tower. (See Photos C-3B, C-4A, and C-7A.) The inspection checklist is on Appendix A-9.

The concrete seat on the control tower is deteriorated, as seen in Photo C-8A and already discussed in the previous section. The wooden deck planking appeared sound except for one or two planks near the control tower. Some other planks felt loose. The deck planking appeared to be bare wood.

3) Outlet Conduit

The outlet conduit consists of a concrete box section 3 feet-2 inches wide by 4 feet high running from the gate well in the bottom of the control tower through the dam to a 4-foot diameter penstock starting just downstream of the downstream toe. The penstock runs about 1.5 miles to Silver Lake. The outlet conduit was not inspected, because access was very difficult and it appeared to be almost completely full of water. The connection between the outlet conduit and the penstock is partially exposed at the downstream toe and is visible in Photos C-4B and C-9A.

4) Spillway and Discharge Channel

The chute type spillway is at the right abutment of the dam (see Overview Photo). The spillway consists of a short approach section, two adjacent concrete weirs at different elevations, and a long chute discharge channel. The inspection checklist is on Appendix A-8.

Photo C-9B shows the approach channel. The floor of the channel is natural bedrock and is obscured, but not significantly obstructed, by grass and weeds.

Photo C-10A shows the lower spillway weir. The remains of the pin-type flashboard supports that have been cut off are visible. At the left in Photo C-10B can be seen the upper spillway weir. Both spillway weirs were in good condition.

The left training wall of the spillway is visible in Photos C-10A, C-10B, and C-11B. Next to the approach section and the weir, the training wall is in good condition. Downstream of the weir on the left of the discharge channel there are several problems. First, there is spalling at two construction joints, one near the first break in slope of the wall top downstream of the weir and the other about 30 feet from the downstream end of

the wall. The joint near the first break in slope is shown in Photo C-11A, which is typical of the condition at the other joint further downstream.

Second, there is significant efflorescence and hairline cracking in the training wall for about 10 feet downstream of the second break in slope downstream of the weir. This is just visible in Photo C-10A to the right of a small evergreen tree growing next to the wall.

Third, at the downstream end of the wall shown in Photo C-11B, there is a transverse crack and the wall is tilted slightly into the discharge channel. The bottom of the wall is undermined at the end, as seen in Photo C-12A. This wall requires maintenance to prevent accelerated deterioration.

There were several logs lodged in the discharge channel just downstream of the weir (see Photo C-10B). Also, there were small evergreen trees and brush growing on the left side next to the training wall (see Photo C-11B).

d. Reservoir Area

It appears that there is well over several feet of sedimentation in the bottom of the reservoir. The design/construction drawings in Appendix B3 indicate that the lowest part of the bottom is about at EL 1280 just upstream and to the right of the intake structure and control tower, at about the natural confluence of Sucker Brook and Dutton Brook. Part of the bottom was visible above the water in this area during the November 7 inspection (see Photo C-3B) and during the aerial photo trip on November 30 (see Overview Photo). The water elevation is judged to be about the same on both occasions and about at EL 1293, slightly above the invert of the intake port (water visible through the racks spilling into the intake in Photo C-7A). This suggests that sedimentation may be built up to as much as 13 feet deep with an average level perhaps several feet lower at about EL 1290. Such a sediment level would bury the inlet of the 24-inch diameter low level drain, which has a top elevation of about EL 1296, located about 25 feet upstream of the intake structure. (Area visible in Overview Photo and Photo C-7B). The inlet of the low level drain was not readily evident from shore during the field inspection, and the reservoir bottom was too soft to allow approaching the suspected location of the inlet.

There does not appear to be any potential hazard due to backwater flooding of the reservoir. Also, other than Sugar Hill Dam located about 2.7 miles upstream on Sucker Brook (see Appendix D-1), no features were observed that might cause excessive alteration of the drainage area or increased inflow. (See separate Phase I Inspection Report for Sugar Hill Dam, VT

00176.) No potential landslide areas were noted around the reservoir.

e. Downstream Channel

All the normal flow from Sucker Brook Reservoir (i.e., all the normal flow of Sucker Brook and Dutton Brook) is diverted through a 4-foot diameter penstock about 1.5 miles long around a mountain to Silver Lake located to the southwest (see Appendix D-1). The beginning of the penstock is shown in Photo C-9A. Any release from the drain pipe at the start of the penstock or seepage from the dam would follow approximately the old natural stream channel of Sucker Brook (visible to the right of the penstock in Photo C-9A and in the vicinity of ponded water in Photo C-6A). About 500 feet downstream of the dam, the spillway discharge channel joins Sucker Brook from the right (see Overview Photo).

From the dam to Lake Dunmore, a distance of about 2 stream miles, Sucker Brook is generally a rocky, sometimes steep channel that is heavily wooded on both sides. For a map of the downstream channel, refer to the Drainage Area Map, Appendix D-1, which also indexes photos that cover the downstream area.

About 0.6 of a mile downstream of the dam (just below Sta 26+00), Voters Brook joins Sucker Brook. About 1 mile downstream (almost to Sta 56+00), an unnamed tributary joins Sucker Brook from the north. Also, approximately at this point any flow from Silver Lake would join Sucker Brook from the south.

About 1.6 miles downstream (Sta 85+00), Sucker Brook runs under a bridge on Town Route 53 (formerly a State highway, see Photo C-12B). Before reaching the bridge, Sucker Brook drops down from the mountains over so-called Lana Falls. Photo C-13A is an aerial overview looking upstream, which shows the mountains in the background and the low-lying area on the shores of Lake Dunmore in the foreground.

Photo C-13B is a closer aerial view of the mouth of Sucker Brook where it flows into Lake Dunmore, and the adjacent low-lying houses and hazard area.

3.2 Evaluation

The hole that was observed beneath the upstream extension of the left training wall of the original spillway should be investigated to see if it passes through the dam and is a potential seepage path. Observation during periods of high water together with dye testing should be tried.

TABLE 5.2

SUCKER BROOK DAM

DAM FAILURE ANALYSIS

CONDITIONS — Top of Dam Elev. 1311.2 (lowest point of non-level top)
 Spillway Crest Elev. 1302
 Total Project Discharge Capacity less
 Diversion Flow at Top of Dam = 4180 cfs ±
 due to two spillways. Outlet works closed.

	Approx. Peak Flow (cfs)	Time to Peak Flow (hours)	Approx. Max. Water Surface			
			Elev. (feet)	Depth (feet)	Top Width (feet)	Avg. Vel. (fps)
<u>PRIOR FLOW AT TOP OF DAM</u>						
Inflow = Outflow = Total Project Discharge Capacity less Diversion Flow at Top of Dam						
Start Routing at Top of Dam						
Dam	4180	--	1311.2	27.2	--	--
Sta 26+00	4180	--	1125.3	5.3	--	28
Sta 80+00	4180	--	644.1	4.1	--	38
Sta 85+00 Hwy Bridge	4180	--	600.6	2.6	--	12
Sta 93+00 Houses	4180	--	580.5	2.5	--	7
<u>BREACH AT TOP OF DAM</u>						
Inflow = zero						
Start Routing at Top of Dam						
Start Breach W.S. at Top of Dam						
Time of Failure = 0.00 hour						
Breach Time = 0.023 hour						
Breach Width = 100 feet						
Breach Depth = 27.2 feet						
Trapezoid, 0.5H:1V side slopes						
Dam	28,000	0.02	1311.2	27.2	--	--
Sta 3+00	--	--	--	--	--	--
Sta 26+00	16,600	0.03	1130.1	10.1	70	40
Sta 56+00	11,100	0.05	899.5	4.5	200	25
Sta 72+00	10,000	0.07	809.5	9.5	50	37
Sta 80+00	10,000	0.07	646.1	6.1	60	46
Sta 85+00 Hwy Bridge	10,000	0.07	601.2	3.2	570	14
Sta 93+00 Houses	7,600	0.10	581.1	3.1	910	7

points. It must be done by judging the calculated quantity, depth, width, and velocity of flow against the real channel cross section as it exists.

b. Results of Analysis

The results of the dam failure analysis using the HEC-1 DB program are summarized in Table 5.2. PRIOR FLOW AT TOP OF DAM establishes initial conditions downstream due to steady state total project discharge capacity, less diversion flow, at the top of dam with no dam breach. The computer input and selected pages of the computer output start on Appendix D-32. In Table 5.2 only the results at the more important stations are summarized.

BREACH AT TOP OF DAM is a major sudden failure of the dam under the conditions previously discussed in Section 5.5.a. Results are summarized in Table 5.2 for all stations, with the computer input and selected pages of the computer output starting on Appendix D-37.

From the computer listing and plot of the breach hydrograph on Appendices D-39 and D-40, note that the standard calculation interval selected (1 minute = 0.017 hours) was short enough to permit the interpolated breach hydrograph at the standard time interval to closely approximate the computed breach hydrograph. Only the interpolated breach hydrograph is routed downstream.

Appendix D-41 is a computer plot of the complete outflow hydrograph during and after the breach.

c. Hazard Evaluation

For a sudden major dam failure, BREACH AT TOP OF DAM, the computed maximum water surface elevation for each downstream station is tabulated in Table 5.2 (Sta 3+00 not used for breach routing) and is plotted on each cross section beginning on Appendix D-28. The top widths of flow determined from each cross section are tabulated in Table 5.2 and are plotted on Appendix D-1 to define the limit of the hazard area, i.e., the limit of flooding due to the dam failure. Also, the computed water surface is shown on the channel profile, Appendix D-31.

The average velocity of peak flow (flow divided by total flow area) is also listed in Table 5.2 for each downstream station for both flow cases. For the dam breach case, the flow area calculation is shown on each cross section plot starting on Appendix D-28, and consists of storage for the channel reach defined by the cross section divided by reach length. The channel storage was computed by the HEC-1 DB program for both flow cases.

Just prior to the dam breach, outflow from the dam was 4180 cfs, and flow 2600 feet downstream was about 5.3 feet deep at about 28 fps. After the breach, peak outflow from the dam

dam was routed downstream using the HEC-1 DB program. Stream conditions just prior to and after the assumed failure were compared. Corps of Engineers' criteria call for breaching the dam with no inflow flood and with the water surface static at the top of the dam, or static at the test flood pool if a test flood of full PMF does not overtop the dam. Since the overtopping analysis shows that the test flood of one-half PMF does overtop the dam, the dam breach was begun at time zero with the water surface at the top of the dam. The contents of the reservoir were routed through the breach as the breach progressed.

To model a sudden major dam breach, maximum breach geometry was selected as follows: constant trapezoidal shape with moderate 0.5H:1V side slopes, breach width across the bottom of the trapezoid equal to the bottom width of the original valley (approximately 100 feet), and a breach depth below the low point on top of the dam equal to 27.2 feet (down to EL 1284), which approximates a full depth failure that would almost completely drain the reservoir. Breach geometry is illustrated on Appendix D-36.

Breach time, or time for the breach width to progress from the top to the bottom of the dam, was selected so that the peak outflow using the HEC-1 DB program would approximate that computed by the Corps of Engineers' "Rule of Thumb" method using the same breach width and depth, plus additional flow equal to total spillway capacity at top of dam, since the breach could be located separate from the spillway. The selection of breach time is shown on Appendix D-36. Rule of Thumb peak breach outflow is about 23,900 cfs. Additional flow due to spillway capacity is 4180 cfs. Therefore, total peak outflow from the dam is about 28,000 cfs. A breach time of 0.023 hours, or 1.38 minutes, was selected for the HEC-1 DB program, which results in a peak outflow of about 28,000 cfs.

The inputted cross sections defining average downstream channel reaches were developed from and are located on the USGS map included as Appendix D-1. Hand plottings of the cross sections start on Appendix D-27, while Appendix D-31 is a profile of the downstream channel. Normal depth channel routing was performed by the HEC-1 DB program using the Manning's n values for left overbank, channel, and right overbank as listed on each cross section plot. The overbank points and the actual channel section in between are only an approximation of the true natural channel. This is because of the constraints of the small scale USGS map that the cross sections were developed from and of the limited 8-point cross section accepted by the program. The third and sixth point on each cross section are defined as the overbank points. Therefore, distinguishing between in-channel and overbank flow cannot be done reliably by simple comparison of computed water surface depth with the defined overbank

TABLE 5.1

SUCKER BROOK DAM

OVERTOPPING ANALYSIS

CONDITIONS — Total Drainage Area = 10.51 Square Miles including Sugar Hill (e)
 Reservoir and its Total Drainage Area of 2.97 Square Miles.
 Start Routing at Spillway Crest Elev. 1302.
 Top of Dam Elev. 1311.2 (lowest point of non-level top)
 Total Project Discharge Capacity at Top of Dam = 4280 cfs ±
 due to two Spillways and Outlet Penstock Fully Open.
 Some Values Rounded from Computed Results.

	TEST FLOOD ONE-HALF PMF (a)
<u>INFLOW</u>	
24-hour Rainfall (inches)	10.6 (b)
24-hour Rainfall Excess (inches) (c)	8.0 (d)
Peak Inflow (cfs)	7290
(csm)	694
<u>OUTFLOW</u>	
Peak Outflow (cfs)	7290
(csm)	694
Time to Peak Outflow (hours)	19.00
Maximum Storage (acre-feet)	63
Max. W.S. Elevation (feet-NGVD)	1313.1
Minimum Freeboard (feet)	overtopped
Maximum Depth over Dam (feet)	1.9
Duration of Overtopping (hours)	5.00

- (a) One-half of full PMF total runoff, including base flow. For one-half PMF base flow = 2 cfs per square mile = 21 cfs ±
- (b) Approximation assuming total losses are the same as for the full PMF. Full PMF 24-hour rainfall equals 18.5 inches.
- (c) Rainfall Excess = Rainfall for the Reservoir Surface. For the rest of the drainage area, losses are assumed to be 1.0 inch initially and 0.1 inch per hour thereafter.
- (d) Equal to one-half of full PMF value. Full PMF 24-hour rainfall excess for the land surface equals 15.9 inches.
- (e) Sugar Hill Dam: Minimum Freeboard = 0.8 foot, peak inflow = 2160 cfs, and peak outflow = 2020 cfs. Routing started with W.S. at spillway crest Elev. 1768.

critical flow over a broad-crested weir) and resulting discharge capacity are included as Appendix D-12. The outlet works were assumed closed. Any flow over the dam was computed by the program assuming critical flow over a non-level dam crest.

Flow from Sugar Hill Reservoir through Subarea 3 to Sucker Brook Reservoir was modeled by the HEC-1 DB program using normal depth channel routing. The inputted cross sections defining average channel reaches were developed from and are located on the USGS map included as Appendix D-1. Hand plottings of the cross sections are included on Appendices D-13 and D-14. The construction and limitations of the cross sections are the same as for the downstream cross sections used in the dam failure analysis as explained later in Section 5.5.a.

f. Overtopping Potential

The results of the overtopping analysis using the HEC-1 DB program are summarized in Table 5.1. The overtopping analysis computer input and complete output for the test flood of one-half PMF are included starting on Appendix D-15.

As noted from Table 5.1, the test flood of one-half PMF overtops the dam by a maximum of about 1.9 feet with duration of overtopping of about 5 hours. Peak inflow for the test flood is 7290 cfs, or 694 csm (cfs per square mile). Peak outflow is unaffected by reservoir routing and is the same as peak inflow, or 7290 cfs, or 694 csm, and occurs about 19 hours after the start of the storm. The peak portion of the inflow and outflow hydrograph for the test flood of one-half PMF is shown by the computer plot on Appendix D-23. Total project discharge capacity at the top of the dam is due to the two-level chute spillway plus the outlet penstock fully open, and is equal to 4280 cfs, or 59% of the test flood peak outflow.

As indicated by footnote (e) on Table 5.1, the test flood of one-half PMF does not overtop Sugar Hill Dam, but results in a minimum freeboard of 0.8 of a foot. Peak inflow is about 2160 cfs. Peak outflow is reduced very little by reservoir routing to about 2020 cfs. Therefore, it appears that Sugar Hill Dam and Reservoir, when starting with a water surface at the spillway crest, does not provide significant flood reduction for Sucker Brook Dam under test flood conditions of one-half PMF.

5.5 Dam Failure Analysis

a. Failure Conditions

In order to evaluate the downstream hazard, the flow just prior to and then due to an assumed major failure or breach of the

square miles or less and was used for this actual 10.51-square-mile drainage area) were inputted to the program as percentages of the index PMP in accordance with HMR 33. A storm reduction coefficient was then applied internally by the program in order to transpose or center the storm over the actual total drainage area. Thus, the corrected 24-hour PMP for the actual total drainage area became 18.5 inches.

In accordance with accepted practice, floods as ratios of the PMF (e.g., one-half PMF) were taken as ratios of runoff, not of precipitation. The HEC-1 DB program applies the ratio to total runoff, including base flow. This method of applying the ratio introduces an increasing error in base flow as the ratio of the PMF gets smaller. However, this error was eliminated by inputting twice the desired base flow to the full PMF, so that one-half PMF, the test flood, would have the correct base flow.

All precipitation was distributed by the program using the Standard Project Storm arrangement of EM 1110-2-1411 (Reference 13), including the percentage distribution for the maximum 6-hour precipitation, and by both the arrangement and percentage distribution from HYDRO-35 (Reference 6) for the maximum 1-hour precipitation.

Appendices D-8 through D-10 summarize the subarea, loss rate, and unit hydrograph data inputted to the program. Five subareas were used (see Appendix D-1). Subareas 1, 3, and 4 consist of all of the land area excluding reservoirs, and Subareas 2 and 5 consist of just Sugar Hill Reservoir and Sucker Brook Reservoir, respectively. For the land in Subareas 1, 3, and 4, loss rates were assumed to be 1.0 inch initially and a constant 0.1 inch per hour thereafter. Snyder unit hydrograph parameters were assumed for average conditions per Appendices D-8 and D-9 and inputted to the program. Conservative standard lag times were used. The program uses the inputted Snyder coefficients to solve by iteration for approximate Clark coefficients, which are then used to calculate the runoff hydrograph.

For the reservoir surfaces making up Subareas 2 and 5, loss rates were set to zero so that rainfall would equal rainfall excess, or runoff. Assuming no delay in the rainfall/runoff response, a constant unit hydrograph for a rainfall duration equal to the HEC-1 DB calculation interval was developed per Appendices D-8 and D-10 and inputted to the program.

Routing through Subarea 2, Sugar Hill Reservoir, was done by the HEC-1 DB program in the same way as in the separate Phase I Inspection Report for Sugar Hill Dam, VT 00176. Inputted stage-area and resulting storage capacity are included as Appendix D-11. Inputted spillway characteristics (for

let conduit and the two spillways was inputted directly to the HEC-1 DB program. Flow over the dam was computed by the HEC-1 DB program, assuming critical flow over a non-level dam crest, using inputted crest length and elevation data (see Appendix B2). The computed results for flow over the dam are hand tabulated on Appendix D-6.

With the reservoir at the low point on the dam crest, EL 1311.2, 9.2 feet over the lower spillway crest, the total discharge from the dam is about 4280 cfs. This is due to the outlet conduit and penstock fully open (about 100 cfs) plus the two-level chute spillway (about 4180 cfs). Also, with an average discharge of about 2140 cfs over the 9.2-foot depth from the top of the dam down to the lower spillway crest, it would take about 11 minutes for the spillway to drain the 33 acre-feet of storage between the top of the dam and the lower spillway crest, or about 1.2 minutes per foot, all assuming no inflow.

d. Selection of Test Flood

Based on the dam failure analysis presented later in Section 5.5, Sucker Brook Dam is classified as having a significant hazard potential (increase in flow due to a dam failure would result in appreciable economic loss and possible loss of less than a few lives caused by damage to portions of Branbury State Park, an increase in damage to a highway bridge on Town Route 53 and the road on either side of the bridge, and flooding of the first floors of about 8 houses along Lake Dunmore to a depth of less than 1 foot, with the moderate flow velocity of 7 fps probably damaging the homes). Since the dam is also classified as small in size (see Section 1.2.c), recommended guidelines of the Corps of Engineers (Reference 1) indicate a test flood in the range of the 100-year flood to one-half PMF (probable maximum flood). Since as many as 8 homes and other facilities are involved in the hazard potential with regard to economic loss, and since the dam is at the upper limit of its small size range with regard to height (36 feet close to the 40-foot limit), the test flood selected for this evaluation was one-half PMF (per Table 5.1, peak inflow = 7290 cfs, peak outflow = 7290 cfs).

The PMF event is that hypothetical flood flow produced by the most critical combination of precipitation, minimum infiltration loss, and concentration of runoff that is considered reasonably possible for a particular drainage area.

e. Development of Test Flood

The index PMP (probable maximum precipitation) inputted to the HEC-1 DB program was 17.5 inches for a 24-hour duration, all-season storm over a 200 square mile basin, according to JMR 33 (Reference 4). Maximum 6-hour, 12-hour, and 24-hour precipitation for the actual size of the drainage area (same for 10

c. Discharge Capacity

The outlet works consists of a gated concrete outlet conduit about 3 feet-2 inches wide by 4 feet high by about 100 feet long from the gate well through the dam. About at the downstream toe, the conduit transitions to a 4-foot diameter penstock about 1.5 miles long to an open channel just short of Silver Lake. (See Appendix D-1.) Originally the penstock was wood stave pipe, but it is thought to have been replaced in recent years with fully paved and coated, smooth-flow corrugated metal pipe.

Assuming the outlet works are fully open, their discharge capacity was found to be strictly a function of the hydraulic capacity of the penstock created by the difference in head between the water surface behind Sucker Brook Dam and the fixed-elevation outlet of the penstock. The formula used and the results of hand computations are shown on Appendix D-5. At the lower spillway crest, EL 1302, the capacity of the outlet conduit and penstock is about 90 cfs. At the dam crest, EL 1311.2, the capacity increases to about 100 cfs.

The only spillway for the dam is a chute spillway at the right abutment. Referring to the engineering data in Appendix B and Photos C-9B, C-10-A, C-10B, and C-11B, the spillway consists of an approach section, two adjacent concrete overflow weir control sections at different elevations, and an excavated earth and rock chute discharge channel, which runs down along the right abutment of the dam and empties into the natural stream channel. The overflow control weirs are 40 feet long and 20 feet long, with crests at EL 1302 and EL 1306, respectively. The lower weir crest is about 5 feet wide and has had its pin-type flashboards removed. The control section has vertical sides on both ends of the weir. The upper weir crest is about 1 foot wide and has no provision for flashboards.

The discharge capacity for each of the two spillways was computed assuming critical flow over a rectangular broad-crested weir. Total spillway capacity was taken as the sum of the capacities of the two spillways. The formulas used and the results of hand computations are shown on Appendix D-6. With water 9.2 feet over the lower spillway crest (i.e., level at the dam crest and 5.2 feet above the upper spillway crest), the two spillways together have a discharge capacity of about 3450 +730 = about 4180 cfs.

Taking the minimum draft elevation for the outlet works at EL 1293, the spillway crests at EL 1302 and EL 1306, and the dam crest at EL 1311.2, total discharge computations are summarized on Appendix D-6 and graphed on Appendix D-7. Total discharge from the dam is the sum of the discharges from the outlet conduit, the two chute spillways, plus flow over the dam for the overtopping condition. The sum of the hand-computed discharges for the out-

5.4 Test Flood Analysis

a. Initial Conditions

The U.S. Army Corps of Engineers Hydrologic Engineering Center's Program HEC-1 DB (Reference 3) was used to develop the test flood hydrology and perform the reservoir routing.

The purpose of this analysis was to evaluate the dam and spillway with respect to their surcharge storage and spillway capacity. Accordingly, it was assumed that the water surface was at the lower spillway crest at the start of the flood routing. Also, it was assumed that the outlet conduit and penstock were fully open as they are normally. The outlet conduit drain pipe was assumed in its normal closed position. Discharge of the low level drain is included in the outlet conduit and penstock.

The effect of Sugar Hill Dam and Reservoir on inflow into Sucker Brook Dam was included in the analysis. The drainage area, storage, and discharge parameters for Sugar Hill Dam are discussed later in Section 5.4.e (calculations on Appendices D-8, D-11, and D-12). It was assumed that the water surface was at the spillway crest at the start of the flood routing.

A constant base flow of 2 cfs per square mile was chosen to represent average conditions in the drainage area and was inputted into the program for all subareas.

b. Storage Capacity

Using a bathymetric map of the reservoir from the original design/construction plans (Appendix B3-7), areas inside contour elevations were measured and the capacity of the reservoir was computed by the method of conic sections. The computations were done by the HEC-1 DB program with the results on Appendices D-22 and D-26. A hand tabulation of the input and the computed results is on Appendix D-2.

The total computed storage capacity at the upper spillway crest (EL 1306) agrees within about 4% of reported values (34 acre-feet or 1.481 million cubic feet (mcf) vs. 1.425 mcf per Appendix B3-3 and 1.5 mcf per Appendices B3-13 and B3-24).

Using the measured and computed values, stage-area and stage-storage curves are presented on Appendices D-3 and D-4, respectively. At the lower spillway crest, EL 1302, the reservoir has a surface area of 3.0 acres and a total capacity of 21 acre-feet. At the dam crest, EL 1311.2, the surface area increases to 4.5 acres and the capacity to 54 acre-feet, or about 17.6 million gallons. Surcharge storage between the spillway crest and the dam crest amounts to 33 acre-feet, or about 0.06 inches of runoff from the 10.51 square mile drainage area. Therefore, the reservoir has almost no capacity to attenuate peak inflow.

SECTION 5

EVALUATION OF HYDRAULICS AND HYDROLOGY

5.1 General

Sucker Brook Dam is shown on the Location and Vicinity Maps at the beginning of this report and on the the Drainage Area Map, Appendix D-1. The dam and the reservoir are located on Sucker Brook in central Vermont at the confluence of Dutton Brook with Sucker Brook. About 10,300 feet downstream of the dam Sucker Brook drains into Lake Dunmore. Lake Dunmore is at the head of the Leicester River which runs westward to the Otter Creek. The Otter Creek runs northward and flows into Lake Champlain, which in turn is drained to the north by the Richelieu River.

The total drainage area at the dam was measured to be about 10.51 square miles, of which about 0.005 square miles (3.0 acres), or less than 0.1%, is the surface area of Sucker Brook Reservoir at the lower spillway crest. (See Appendices D-1 and D-2). The measured total drainage area is as much as about 21% larger than that reported in existing engineering data (10.51 square miles measured vs. 8.7 to 9.0 square miles reported in Appendices B3-3, B3-11, and B3-24). Being in the northwestern foothills of the Green Mountain National Forest, the topography is characterized by wooded slopes averaging 5% to 20%. The elevation of the drainage area varies approximately from EL 1293 to EL 3230.

Upstream of this dam is the Sugar Hill Reservoir, which has a drainage area measured to be about 2.97 square miles. This drainage area is included as part of the total drainage area for Sucker Brook Dam. Therefore, about 28% of the total drainage area of Sucker Brook Dam is regulated by Sugar Hill Reservoir. The measured drainage area tributary to Sugar Hill Dam is as much as about 29% larger than that reported in existing engineering data (2.97 square miles measured vs. 2.3 to 2.5 square miles reported in Appendices B3-3, B3-11, and B3-24).

5.2 Design Data

There are no known records of the hydraulic and hydrologic criteria used in the original design of the dam and reservoir. The engineering data which was available, mainly old design and reconstruction plans and reports of construction, are discussed in Section 2 of this report.

5.3 Experience Data

There are no known records of routine water levels and discharges or of past floods at the dam. However, according to the available data in Appendix B3, it is known that a flood occurred in September of 1938 which caused extensive damage to the spillway channel necessitating its relocation.

4.2 Maintenance Procedures

a. General

According to the Owner, maintenance crews visit and inspect the dam once a week and perform routine maintenance, such as brush clearing, annually. There are no written maintenance procedures for the dam and reservoir and their operating facilities.

b. Operating Facilities

(Covered under preceding Section 4.2.a - General.)

4.3 Evaluation

Written operation and maintenance procedures for this dam do not exist. Although routine maintenance of the dam is said to occur annually, our visual inspection suggests that slope maintenance, for instance, has been rather irregular and less often than yearly. Brush growth and tree stumps were evident on the slopes. Effective operation and maintenance procedures need to be developed and implemented by the Owner in order to avoid deterioration of the dam.

As part of the operation procedure, the Owner should formalize the reservoir regulation plan that is now used to maintain normal water level below the spillway crest. This is necessary due to the dam's inadequate spillway capacity when starting with a normal pool at the spillway crest (see Sections 5 and 7), and due to questions about the physical condition of the dam and spillway (see Sections 3, 6 and 7).

SECTION 4

OPERATION AND MAINTENANCE PROCEDURES

4.1 Operation Procedures

a. General

Sucker Brook Reservoir was originally used as a diversion and storage reservoir as part of the Silver Lake Hydroelectric Development. Presently, the reservoir is used only to divert water with the normal water level reportedly being maintained well below the spillway crest. At the time of inspection, the reservoir was almost empty, about down to the level of the intake port at the base of the control tower, which is about 9 feet below the lower spillway crest. The slide gate in the gate well under the control tower was open, and it allowed continuous outflow from the dam through the penstock to Silver Lake. Apparently the slide gate is left fully open so that as much water as possible is diverted to Silver Lake. Except for heavy flows in the spring, it appears that all the normal flow of Sucker and Dutton Brooks is diverted to Silver Lake.

The chute spillway is ungated and wide open, and its flashboards have been cut off by the Owner. (See Photo C-10A.) Reportedly the spillway operates only in the spring when a large amount of inflow into the reservoir occurs.

There are no written operation procedures for the dam and reservoir.

The Owner indicates that the dam is inspected annually by the firm of Kleinschmidt and Dutting, Engineering Consultants, 70 Main Street, Pittsfield, Maine 04967, telephone (207) 487-3328. However, the Owner did not make the results of those inspections available for review.

b. Emergency Action Plan and Warning System

An emergency action plan with a warning system is in effect for Sucker Brook Dam, according to the Owner. It involves stationing a company employee with a radio at the dam during severe storm events. If an emergency situation develops, he alerts a dispatcher who then informs State Police and local Town officials of the situation.

According to the Owner, the emergency action plan is in writing. However, the Owner would not produce a copy for review or inclusion in this report.

Logs lodged in the spillway discharge channel should be cleared. Also, all brush and small trees in the spillway discharge channel, particularly next to the training wall, should be removed.

The cause of the scarps near the upstream toeline approximately opposite the leftmost angle point of the dam should be investigated. The scarps should be monitored until such time as they are investigated.

The brush and small trees should be cut from all slopes annually to a distance of about 20 feet from the toeline. Existing rotting stumps and their roots on the downstream slope should be removed and replaced with proper backfill.

The clear seepage that was observed exiting from the rock cover at the downstream toeline should be monitored at least annually.

The deteriorated concrete seat for the service bridge on the control tower should be repaired. Also, the vertical crack in the left side of the control tower should be investigated and repaired.

The inside of the intake structure, the gate well under the control tower, and the outlet conduit should be dewatered and thoroughly inspected. The service slide gate should be inspected and its operation checked.

The low level drain should be exposed if buried by sediment and its condition checked.

The depth of sediment in the reservoir - suspected to be well over several feet and covering the low level drain - should be verified. Sediment should be cleaned out at least down to the level of the low level drain. This will help to eliminate the trash and leaves that collect against the intake rack, and which should be kept cleaned off.

The left end of the lower horizontal pipe railing on top of the control tower toward the intake should be secured by replacing the missing piece.

One or two wooden deck planks on the service bridge near the control tower appear weak and should be replaced. All planks should be kept bolted tightly. Also, a preservative should be considered for the apparently bare wooden decking.

The downstream end of the left training wall of the spillway discharge channel should be repaired or rebuilt where it is cracked and undermined. Also, spalling at two construction joints in the training wall should be repaired. The significant hairline cracking and efflorescence near the second break in slope of the wall top downstream of the spillway weir should be repaired.

increases about 6.7 times to 28,000 cfs. This causes water at Sta 26+00 to rise from 5.3 to 10.1 feet deep, an increase of 4.8 feet, which floods an area about 70 feet wide. Velocity increases about 1.4 times to 40 fps.

At Sta 85+00 at the highway bridge on Town Route 53 (formerly a State highway), peak flow increases about 2.4 times to 10,000 cfs after the breach. This causes the water to rise from 2.6 to 3.2 feet deep, an increase of 0.6 foot, which floods an area about 570 feet wide. Velocity increases about 1.2 times to 14 fps. The highway bridge, which is visible in Photo C-12B, has an estimated capacity (Reference 17) of only 1000 to 1500 cfs with headwater 8 feet deep (i.e., water level with the road), which is less than even the prior flow of 4180 cfs. Therefore, the increase in flow due to the dam failure would only worsen the already out-of-channel and over-the-roadway flow condition that would exist just prior to the failure.

At Sta 93+00 near houses along Lake Dunmore, peak flow increases about 1.8 times to 7600 cfs after the breach. This causes the water to rise from 2.5 to 3.1 feet deep, an increase of 0.6 of a foot, which floods an area about 910 feet wide. Velocity remains the same at about 7 fps. Ground around the houses is estimated at EL 580 with the first floors estimated at EL 581. Prior flow at EL 580.5 appears to not quite flood the first floors. The 0.6-foot increase due to the dam failure appears to flood the first floors to a depth of less than 1 foot. The 7 fps velocity would probably damage the structures. It is estimated that about 8 houses would be involved in this flooding, plus miscellaneous outbuildings. An adjacent State Park would also be flooded and damaged.

The flood routing was not carried any further downstream than Sta 93+00 because Sucker Brook drains into Lake Dunmore just after this station. Lake Dunmore has a surcharge storage capacity of over 1035 acre-feet per foot as compared to the total volume of Sucker Brook Reservoir at the top of dam of only about 54 acre-feet. Therefore, it appears that a failure of Sucker Brook Dam would have a negligible effect on Lake Dunmore and any other area further downstream.

In summary, it appears that the increase in flow due to a failure of the dam would damage portions of Branbury State Park and flood the first floors of about 8 houses along Lake Dunmore to a depth of less than 1 foot, with the moderate flow velocity of 7 fps probably damaging the structures. Damage to a highway bridge on Town Route 53 and to the road on either side of the bridge would only be increased by a dam failure. Total economic loss is judged appreciable. Loss of less than a few lives is judged possible. Therefore, according to recommended guidelines (Reference 1), the dam is classified as having a significant hazard potential.

SECTION 6

EVALUATION OF STRUCURAL STABILITY

6.1 Visual Observations

The presence of a hole on the upstream side of the dam adjacent to the concrete wall that apparently passes transversely through the dam is a feature that may lead to future internal erosion. This feature, described in Section 3.1.b, is located on the upstream end of the concrete wall near the rightmost angle point in the dam.

In a Nov. 27, 1939 letter (Appendix B3-19), H.K. Barrows indicated that the above-mentioned wall, which formed the left training wall of a former spillway, was to be removed prior to extending the embankment. The embankment was extended to construct a new spillway subsequent to the 1938 flood. It is not known whether the wall was actually removed or what precautions were taken to ensure that a waterstop was present along this wall. Also, it is not known whether the original spillway crest was buried in the new embankment.

During periods when the water level in the reservoir rises above this hole, an inspection should be made to determine whether there is any sign of flow into the hole. A careful examination should be made at the same time of the downstream side of the dam to detect any outflow that is observable. Dye-tracing techniques may be valuable for this purpose.

The small scarps that exist near the upstream toeline approximately opposite the leftmost angle point in the dam (see Section 3.1.b) may be due to placement of embankment fill over a highly organic soil. Excavation into these small scarps to examine the subsoils would be desirable to determine whether any conditions exist that require repair. Measurements should be made on a periodic basis to determine whether the scarps are presently deforming.

The presence of tree stumps that were cut many years ago and left in the downstream slope indicates that rotting roots are in the embankment. These roots may create channels where flow will concentrate and erode the dam internally. Such an effect is not serious in dams which are zoned with a pervious downstream shell.

6.2 Design and Construction Data

The dam is on a clay foundation, according to the April 17, 1951 inspection report by Stephen H. Haybrook (Appendix B3-24). The presence of clay in the foundation has not caused any obvious differential settlement of the crest.

In the original (1937) report by H. K. Barrows (Appendix B3-11), he indicated that the foundation material is a "clay hardpan". If this is the case, settlements would not be expected to occur.

The plans submitted in connection with the 1937 construction permit application to the State of Vermont (see Appendix B3-6) indicate that this dam was to be zoned. The upstream and downstream shells were to be free-draining material, whereas the center was to be composed of clay hardpan from a nearby borrow pit. However, the report submitted by Barrows to the Vermont Public Service Commission on Nov. 20, 1937 (Appendix B3-11), indicates the use of a rockfill toe on the downstream side of a homogeneous embankment of "hardpan." There is no indication that a filter was placed between the rockfill toe and the hardpan. It was mentioned, however, that the hardpan was well graded.

6.3 Post-Construction Changes

One year after construction of this dam, the 1938 hurricane struck Vermont. The flood "caused the spillway channel below the dam to be so badly washed as to necessitate the reconstruction of the channel." (See Nov. 27, 1939 letter by H.K. Barrows, Appendix B3-19.) Therefore, the spillway was moved to the right onto a bedrock foundation. The spillway length was reduced from 150 feet to 40 feet, but its permanent crest elevation was lowered 4 feet. Flashboards that would break when the head over the spillway crest was 5.3 feet (leaving 4.7 feet of freeboard to the design dam crest) were installed. These flashboards are no longer in place.

6.4 Seismic Stability

This dam is in Seismic Zone 2. Therefore, according to recommended guidelines (Reference 1), a seismic stability analysis is not warranted.

SECTION 7

ASSESSMENT, RECOMMENDATIONS, AND REMEDIAL MEASURES

7.1 Dam Assessment

a. Condition

Sucker Brook Dam is in FAIR condition. Significant problems include several scarps near the upstream toe line about opposite the leftmost angle point of the dam; brush and small trees on the embankment slopes with some larger stumps on the downstream slope; cracking and undermining of the downstream end of the left concrete training wall of the spillway discharge channel; and what appears to be a significant amount of reservoir sedimentation that reduces total storage capacity and could hinder operation of the low level drain. Also, a hole was observed beneath the upstream extension of the left training wall of the original spillway (now covered with embankment) that could be a potential seepage path through the embankment.

The spillway is INADEQUATE to pass the test flood without overtopping the dam. In accordance with recommended guidelines of the Corps of Engineers, the dam is classified as SMALL in size and as having a SIGNIFICANT hazard potential. Accordingly, a TEST FLOOD equal to ONE-HALF PMF (probable maximum flood) was judged as appropriate within the recommended range of the 100-year flood to one-half PMF. The test flood overtops the dam by a maximum of about 1.9 feet with duration of overtopping of about 5 hours. Peak inflow for the test flood is 7290 cfs. Peak outflow is unaffected by reservoir routing and is the same as peak inflow, or 7290 cfs. Total project discharge capacity at the top of the dam is due to the two-level chute spillway plus the outlet penstock fully open, and is equal to 4280 cfs, or 59% of the test flood peak outflow.

b. Adequacy of Information

This Phase I Inspection was based primarily on the visual inspection and the hydraulic and hydrologic computations performed, coupled with sound engineering judgement. The visual inspection was done when the pool was very low, about 18 feet below the top of an approximately 36-foot high dam. Available data consisted of a letter and two reports on construction of the dam and relocation and construction of the new spillway 2 years later, including poor copies of four various design/construction drawings, together with one report of an inspection some years later. Such data as the design calculations, construction specifications, detailed data on the foundation and embankment soils, and detailed operation and performance data were not available. The lack of such in-depth engineering data does not

permit a comprehensive review. Therefore, the adequacy of this dam could not be assessed with respect to reviewing design, construction, and operation data.

c. Urgency

WITHIN ONE YEAR after their receipt of this Phase I Inspection Report, the Owner should implement the recommendations given in Section 7.2 and the remedial measures given in Section 7.3

7.2 Recommendations

WITHIN ONE YEAR after their receipt of this Phase I Inspection Report, the Owner should engage a registered engineer qualified in the design of dams to do the following work and provide the consequent recommendations. The Owner should implement those recommendations.

- a. Determine whether the hole that was observed beneath the upstream extension of the left training wall of the original spillway passes through the dam. If so, provide recommendations on any necessary repairs.
- b. Investigate the cause of the scarps near the upstream toe line approximately opposite the leftmost angle point in the dam.
- c. Advise how to repair or rebuild the downstream end of the left training wall of the spillway discharge channel where it is cracked and undermined.
- d. Select appropriate backfill for root holes left after removal of roots and stumps (see Section 7.3.a.2).
- e. Investigate and advise on the vertical crack in the left side of the concrete control tower.
- f. Perform a detailed hydraulic and hydrologic study to better evaluate spillway capacity. Any detailed hydrologic work should take into account all upland storage that may exist in the drainage area that would tend to reduce inflow. If necessary, spillway capacity should be increased by new design and construction.
- g. Check the hydraulics of the spillway discharge channel to see if the left training wall would be overtopped during heavy flows, and if so, make recommendations.

7.3 Remedial Measures

a. Operation and Maintenance Procedures

WITHIN ONE YEAR after their receipt of this Phase I Inspection Report, the Owner should implement the following operation and maintenance procedures:

- 1) Cut the brush and small trees from all slopes annually to a distance of about 20 feet downstream from the toeline.
- 2) Remove and replace the roots of rotting stumps on the downstream slope with a properly selected, compacted backfill.
- 3) Monitor the clear seepage that was observed exiting from the rock cover at the downstream toeline.
- 4) Monitor the scarps (Section 7.2.b) until such time as they have been investigated.
- 5) Repair the spalling at two construction joints in the left training wall of the spillway discharge channel. The significant hairline cracking and efflorescence near the second break in slope of the wall top downstream of the spillway weir should be repaired.
- 6) Clear the logs lodged in the spillway discharge channel. Also, all brush and small trees in the channel, particularly next to the training wall, should be removed.
- 7) Repair the deteriorated concrete seat for the service bridge on the control tower.
- 8) Dewater and thoroughly inspect the inside of the intake structure, the gate well under the control tower, and the outlet conduit. The service slide gate should be inspected and its operation checked.
- 9) Expose and check the condition of the low level drain, which is suspected of being buried by sediment.
- 10) Verify the depth of sediment in the reservoir. Sediment should be cleaned out at least down to the level of the low level drain. Keep the trash and leaves cleaned off the intake rack.
- 11) Secure the left end of the lower horizontal pipe railing on top of the control tower by replacing the missing piece.

- 12) Replace one or two weak wooden deck planks on the service bridge near the control tower. All planks should be kept bolted tightly. A preservative should be considered for the apparently bare wooden decking.
- 13) Develop and implement effective operation and maintenance procedures to avoid deterioration of the dam.
- 14) Continue to carry out an annual technical inspection of the dam and make repairs as needed.
- 15) Make any improvements necessary in the existing emergency action plan and warning system to ensure proper and timely action during critical periods.

7.4 Alternatives

No practical alternatives exist to the recommendations and remedial measures contained in this report.

APPENDIX A

INSPECTION CHECKLIST

VISUAL INSPECTION CHECKLIST DAM INSPECTION

DAM SUCKER BROOK DAM DATE November 7, 1979
 ID NO. VT 00212 TIME 1300 - 1530
 TOWN Salisbury WEATHER Drizzly, Overcast, 45° F
 COUNTY Addison W.S. ELEV. 1293+ UPSTREAM
 STATE Vermont 1275+ DOWNSTREAM

INSPECTION PARTY

RECORDER (X)

1. Thomas Bennedum, Gordon E. Ainsworth & Assoc., Inc. X
2. Edwin Vopelak, Jr., Gordon E. Ainsworth & Assoc., Inc.
3. John Kenworthy, Gordon E. Ainsworth & Assoc., Inc.
4. Steve J. Poulos, Geotechnical Engineers, Inc. X
5. Peter Barranco, Jr., Vermont Dept. of Water Resources
6. J. Douglas Graham, Manager of Hydraulic Generation, Central Vermont
Public Service Corporation (CVPS)
7. _____
8. Edward Lurvey, General Hydraulic Foreman, CVPS
9. _____
10. _____

PROJECT FEATURE/DISCIPLINE	INSPECTOR	REMARKS
1. <u>H & H</u>	<u>T. Bennedum</u>	<u>-</u>
2. <u>Geotechnical</u>	<u>S. Poulos</u>	<u>-</u>
3. <u>Structural</u>	<u>T. Bennedum</u>	<u>-</u>
4. <u>Mechanical</u>	<u>T. Bennedum</u>	<u>-</u>
5. <u>Electrical</u>	<u>None</u>	<u>N/A</u>
6. _____	_____	_____

VISUAL INSPECTION CHECKLIST

PROJECT SUCKER BROOK DAM DATE Nov. 7, 1979
 PROJECT FEATURE NAME
 DISCIPLINE Geotechnical NAME S. J. Poulos

AREA EVALUATED		CONDITION
<u>DAM EMBANKMENT</u>		
	Crest Elevation	EL 1311.2
	Current Pool Elevation	EL 1293 +
	Maximum Impoundment to Date	Unknown
GEI	4 Surface Cracks	None observed.
GEI	5 Pavement Condition	No pavement. Partially bare dirt road.
GEI	6 Movement or Settlement of Crest	Small (6 in.) dip in crest about 180 ft left of spillway wall. Otherwise not observable.
GEI	7 Lateral Movements	None observed.
GEI	Vertical Alignment	See item 6.
GEI	Horizontal Alignment	Not observable.
GEI	Condition at Abutment and at Concrete Structures	Good at left and right walls of spillway, at intake structure, and at old wall that passes transversely across embankment. Undermining of upstream end of concrete wall at upstream toe of dam, about 100 ft left of left spillway wall. Left abutment good. Stones have been placed in erosion gully 1-2' deep of left downstream contact line. Other contacts ok. Two rodent holes (fresh) seen on downstream face 10' below crest 50' right of left abutment. These contain silty coarse sand. Three chuckholes in earth below downstream toe. One hole 4" in. dia. at upstream toe near angle point in dam.
GEI	Indications of Movement of Structural Items on Slopes	None observed.
GEI	Trespassing on Slopes	Free access.
GEI	Sloughing or Erosion of Slopes or Abutments	Two scarps, 6 to 12 in. high, at left angle point in dam on u.s. slope about 3 ft and 6 ft downstream from pool shoreline. A few bare spots on upstream and downstream slopes.
A-2		

VISUAL INSPECTION CHECKLIST

PROJECT SUCKER BROOK DAM DATE Nov. 7, 1979
 PROJECT FEATURE NAME
 DISCIPLINE Geotechnical NAME S. J. Poulos

JEI
JEI
JEI
JEI
JEI
JEI
JEI
JEI

AREA EVALUATED

CONDITION

Rock Slope Protection - Riprap Failures

Riprap covers upstream slope non-uniformly. Appears unfiltered.

Unusual Movement or Cracking at or Near

None observed near downstream toe. See above "Sloughing or Erosion..." for upstream slope.

Unusual Embankment or Downstream Seepage

Stream flowing clear at about 4 gpm in original stream channel below dam. No other seeps observed.

Piping or Boils

None observed.

Foundation Drainage Features

None.

Toe Drains

None.

Instrumentation System

None.

Vegetation

Upstream: Bushes to 5' high and grass down to riprap. Riprap overgrown. Downstream: Small balsam, spruce, and white birch beginning to grow. Raspberry and other bushes to 5' high. Old stumps to 8" dia., now rotted.

VISUAL INSPECTION CHECKLIST

DAM SUCKER BROOK DAM DATE Nov. 7, 1979

DISCIPLINE Structural/H & H INSPECTOR T. Bennedum

DISCIPLINE Geotechnical INSPECTOR S.J. Poulos

4

AREA EVALUATED	CONDITION
<p><u>OUTLET WORKS - INTAKE CHANNEL AND INTAKE STRUCTURE</u></p> <p>a. Approach Channel</p> <p>Slope Conditions</p> <p>Bottom Conditions</p> <p>Rock Slides or Falls</p> <p>Log Boom</p> <p>Debris</p> <p>Condition of Concrete Lining</p> <p>Drains or Weep Holes</p> <p>b. Intake Structure</p> <p>Condition of Concrete</p> <p>Stop Logs and Slots</p> <p>A-4</p>	<p>Heavily forested.</p> <p>Natural old bog. Bottom is visible. Organic soils and grass cover the bottom.</p> <p>None.</p> <p>None.</p> <p>Trash & leaves around intake. Some trees higher on banks.</p> <p>N/A</p> <p>N/A</p> <p>Partially underwater.</p> <p>Fair to good.</p> <p>None observed.</p> <p>Large wooden trash rack structure over inclined intake port. Rack structure in fair to good condition.</p>

VISUAL INSPECTION CHECKLIST

DAM SUCKER BROOK DAM DATE Nov. 7, 1979

DISCIPLINE Structural/Mechanical INSPECTOR T. Bennedum

DISCIPLINE No Geotechnical Features INSPECTOR -

5

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - CONTROL TOWER</u>	
a. Concrete and Structural	
General Condition	Good, except for crack.
Condition of Joints	N/A
Spalling	None. (See Service Bridge, A-9)
Visible Reinforcing	None.
Rusting or Staining of Concrete	At vertical crack on left side.
Any Seepage or Efflorescence	None.
Joint Alignment	N/A
Unusual Seepage or Leaks in Gate Chamber	Inside not observable.
Cracks	Vertical crack on left side at pipe socket.
Rusting or Corrosion of Steel	None observed.
b. Mechanical and Electrical	
Air Vents	Top of structure open.
Float Wells	None.
Crane Hoist	None.
Elevator	None.
Hydraulic System	None.
Service Gates	Not observable. In gate well.
Emergency Gates	Control mechanism O.K.
Lightning Protection System	None.
Emergency Power System	None.
Wiring and Lighting System	None.
	Railing on U/S side toward rack structure loose - broken weld.
A-5	

VISUAL INSPECTION CHECKLIST


DAM SUCKER BROOK DAM DATE Nov. 7, 1979

DISCIPLINE Structural/H & H INSPECTOR T. Bennedum

DISCIPLINE No Geotechnical Features INSPECTOR -

6

AREA EVALUATED	CONDITION
<p><u>OUTLET WORKS - TRANSITION AND CONDUIT</u></p> <p>General Condition of Concrete</p> <p>Rust or Staining on Concrete</p> <p>Spalling</p> <p>Erosion or Cavitation</p> <p>Cracking</p> <p>Alignment of Monoliths</p> <p>Alignment of Joints</p> <p>Numbering of Monoliths</p> <p style="text-align: right;">A-6</p>	<p>Not observable. Access difficult and partially underwater. Consists of 3'-2" wide x 4' high concrete box section outlet conduit from gate well through dam to 4'-dia. penstock beginning just after D/S toe. Penstock runs about 1.5 miles to Silver Lake. Connection to penstock consists of a concrete transition to a round section, followed by a 47 3/4"-dia. steel pipe section, w/20"-dia. drain pipe to side, and then a partially exposed corrugated metal pipe connection to the penstock.</p>



Salisbury in the county of Addison aforesaid, in which said proposed diversion dam is located, and has delivered to said selectmen a copy thereof.

WHEREFORE, your petitioner prays:

That your Honorable Commission may review the plans and specifications hereinabove set forth and referred to and annexed hereto, and make such additional investigation through such engineers or in such other manner as said Public Service Commission shall deem necessary respecting said dam, and shall thereupon make and issue its order approving such construction, all in accordance with the provisions of Sections 6122 to 6130 of the Public Laws in such case made and provided, and for such other and further order in the premises as shall be proper.

Dated at City of Rutland, in the County of Rutland and State of Vermont this 27th day of May, A. D. 1937.

CENTRAL VERMONT PUBLIC SERVICE CORPORATION

By *John C. M. Morse*

Its Attorneys

The total drainage area above the proposed dam is 8.7 square miles, 2.3 square miles of which is now controlled by the so-called "Sugar Hill Reservoir" of said petitioner located in Coshon, in the County of Addison, constructed under the permission, authority and order of your Honorable Commission in proceeding No. 1697 dated January 21st, 1932. The capacity of the pond which will be created by said proposed dam at spillway elevation 1306 is 1,425,000 cubic feet.

The intake structure for the pipe line will be bottlenecked on ledge and constructed as set forth in detail on the map hereto attached marked 412-33; the details of construction of the pipe line and intake pipe attached thereto leading from said dam being set forth on map hereto attached marked 412-36. Attached hereto is a graph or chart numbered 412-35 showing pondage and spillway capacity of said diversion dam by curves.

On Map 412-32 there is delineated the location of a concrete and rubble masonry dam located upstream on Dutton Brook and extending across Sucker Brook, which has been formerly used for a diversion dam for like purposes, but which dam is now to be abandoned but is to be left in place to collect any silt or gravel deposit and protect the intake of the proposed dam from damage which might result therefrom.

The work of construction of said proposed dam is to be performed by Sanders Engineering Company under the engineering direction of Frank H. Mason, Civil Engineer for Nepsco Services, Inc.

Your petitioner further represents that it has given notice of this petition to the selectmen of said town of

upon a copy of the United States Geological Survey Map for the Brandon Quadrangle attached hereto. As will appear from the notation on the right hand margin of said map the junction of Sucker and Ditton Brooks above referred to is inaccurately shown thereon as being in the town of Leicester, when in fact said junction of said streams is in the town of Salisbury. Said locations are further shown on a map or drawing No. S.L. 59 attached hereto.

Your petitioner proposes to construct a dam hereinafter described at the junction of said two streams for the purpose of collecting, storing and diverting the waters of said streams by means of a pipe line or penstock into Silver Lake, so-called, and thence by means of another pipe line of said petitioner now in use to its Silver Lake generating station, so-called, as outlined on said map above referred to.

The plans for the proposed construction of said dam and intake to said pipe line contemplate that the dam will be founded upon a good clay foundation to be constructed of an earth embankment with a clay core. The maximum height of the proposed dam to be forty (40) feet with an average height of approximately thirty (30) feet. The top of said dam to be at elevation 1312 M.S.L. The width at the top of said dam to be ten (10) feet with two to one slopes on both upstream and downstream sides, the width of the base necessarily varying according to the height of the dam, said slopes to be rip-rapped with extra heavy rip-rapping at the toe of said dam on both slopes, and the full length of the upstream slope. The length of the spillway to be one hundred fifty (150) feet. All in accordance with a general plan and cross-sections thereof set forth on the plan annexed hereto marked 412-32.

STATE OF VERMONT

ADDISON COUNTY

VERMONT PUBLIC
SERVICE COMMISSION

MAY 29 1937

IN RE: PETITION OF)
CENTRAL VERMONT PUBLIC SERVICE)
CORPORATION FOR AUTHORITY TO)
CONSTRUCT A DAM ON SUCKER BROOK,)
SO-CALLED, IN SALISBURY, VERMONT)

RECEIVED

Before
Public Service
Commission

P E T I T I O N

To the Honorable Public Service Commission, within
and for the State of Vermont:

The Central Vermont Public Service Corporation, a
corporation organized under the laws of the State of Vermont,
and having its principal place of business in the City of
Rutland, in the County of Rutland and State of Vermont,
respectfully represents:

THAT it is a corporation engaged in the generation,
manufacture and sale of electricity to the public for
heating, lighting and power purposes, and is subject to the
jurisdiction of the Public Service Commission of Vermont.

THAT it is the owner of certain lands, rights, ease-
ments, and water rights in the towns of Leicester, Salisbury
and Goshen, all in the County of Addison, and particularly
of certain lands, water rights and easements in Sucker Brook,
so-called, and on Dutton Brook, so-called, the general
location of the streams and drainage area being set forth



APPENDIX B

SECTION B3

COPIES OF PAST INSPECTION REPORTS AND DATA

TABLE OF CONTENTS

	<u>Page</u>
Petition of Central Vermont Public Service Corporation to Vermont Public Service Commission (with 4 drawings) - May 27, 1937	B3-1
Letter on Sucker Brook Diversion Dam by H.K. Barrows - June 18, 1937	B3-9
Report on Sucker Brook Diversion Dam (with drawing) by H.K. Barrows - November 20, 1937	B3-11
Order Approving Dam Construction from Vermont Public Service Commission - December 8, 1937	B3-18
Report on Sucker Brook Spillway Improvement (with drawing) by H.K. Barrows - November 27, 1939	B3-19
(Inspection) Report on Sucker Brook Dam by Stephen H. Haybrook - April 17, 1951	B3-24



FIELD WORK - NOVEMBER 7, 1979

SUCKER BROOK DAM FIELD MEASUREMENTS PHASE I INSPECTION APPENDIX B2

GORDON E AINSWORTH & ASSOCIATES INC

20 SUGARLOAF ST SOUTH DEERFIELD MASS 01353



f. Vermont Public Records
133 State Street
Montpelier, Vermont 05602
(802) 828-3280

- 1) PSC petition and approval
- 2) drawings
- 3) letter and reports

APPENDIX B

SECTION B1

LISTING OF LOCATIONS FOR AVAILABLE RECORDS AND DATA

- a. Owner: Central Vermont Public Service Corporation
77 Grove Street
Rutland, Vermont 05701
Attention: J. Douglas Graham,
Manager of Hydraulic Generation
(802) 773-2711
- 1) drawings
 - 2) inspection reports
 - 3) warning system
- (Details and extent of data not known due to unwillingness of Owner to make such information available.)
- b. Designer of Present Dam:
- New England Public Service Corporation
(NEPSCO)
(Location and business status unknown.)
- c. Contractor for Present Dam:
- Sanders Engineering Company
(Location and business status unknown.)
- d. Agency of Environmental Conservation
Department of Water Resources
Water Quality Division
Montpelier, Vermont 05602
Attention: A. Peter Barranco, Jr., P.E.
Dam Safety Engineer
(802) 828-2761
- 1) inspection reports
- e. Vermont Public Service Board
State Office Building
120 State Street
Montpelier, Vermont 05602
Attention: Wayne Foster, Utility Engineer
(802) 828-2326
- 1) case numbers

APPENDIX B

ENGINEERING DATA

<u>Section</u>	<u>Description</u>
B1	Listing of Locations for Available Records and Data
B2	Drawings (See B3-6 thru 8 & B3-23)
B3	Copies of Past Inspection Reports and Data

VISUAL INSPECTION CHECKLIST

DAM SUCKER BROOK DAM DATE Nov. 7, 1979
 DISCIPLINE Structural. INSPECTOR T. Bennedum
 DISCIPLINE No Geotechnical Features INSPECTOR -

9

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - SERVICE BRIDGE</u>	
a. Super Structure	
Bearings	OK.
Anchor Bolts	OK.
Bridge Seat	OK.
Longitudinal Members	Open web beams. Good shape.
Underside of Deck	OK.
Secondary Bracing	Steel channel. OK.
Deck	2"x6" wood planks. Some loose. One or two near tower are poor. Runs off and through.
Drainage system	
Railings	Steel pipe. Good.
Expansion Joints	End on dam appears free to move.
Paint	Good on steel. Wood bare.
b. Abutment & Piers	
General Condition of Concrete	Poor on control tower seat.
Alignment of Abutment	OK.
Approach to Bridge	OK. Walk down from crest.
Condition of Seat & Backwall	Poor. Cracked & broken concrete on tower seat.
A-9	

VISUAL INSPECTION CHECKLIST

DAM SUCKER BROOK DAM. DATE Nov. 7, 1979

DISCIPLINE Structural/H & H INSPECTOR T. Bennedum

DISCIPLINE Geotechnical INSPECTOR S.J. Poulos

8

AREA EVALUATED	CONDITION
<p><u>OUTLET WORKS - SPILLWAY WEIR, APPROACH AND DISCHARGE CHANNELS</u></p> <p>a. Approach Channel</p> <p>General Condition</p> <p>Loose Rock Overhanging Channel</p> <p>Trees Overhanging Channel</p> <p>Floor of Approach Channel</p> <p>b. Weir and Training Walls</p> <p>General Condition of Concrete</p> <p>Rust or Staining</p> <p>Spalling</p> <p>Any Visible Reinforcing</p> <p>Any Seepage or Efflorescence</p> <p>Drain Holes</p> <p>c. Discharge Channel</p> <p>General Condition</p> <p>Loose Rock Overhanging Channel</p> <p>Trees Overhanging Channel</p> <p>Floor of Channel</p> <p>Other Obstructions</p>	<p>One spillway with two adjacent weirs, 4' between crest elevations.</p> <p>Fair.</p> <p>None.</p> <p>Forested, trees overhanging on right side.</p> <p>Natural stream channel in bedrock.</p> <p>Good.</p> <p>Rust at cut-off flashboard pins.</p> <p>At 2 const. joints in left training wall, one near 1st break in slope & other 30' from D/S end.</p> <p>None.</p> <p>Effl. at H/L cracking for 10' D/S of 2nd break in slope on left TW. 2-3 inch dia. 4 feet o.c., 4 ft. and 8 ft. down from top of left D/S training wall. N/A on right.</p> <p>Good.</p> <p>None.</p> <p>Forested. Trees overhanging on right.</p> <p>Natural bedrock.</p> <p>Logs trapped in channel from previous flows.</p>

VISUAL INSPECTION CHECKLIST

DAM SUCKER BROOK DAM DATE Nov. 7, 1979

DISCIPLINE Structural/H & H INSPECTOR T. Bennedum

DISCIPLINE Geotechnical INSPECTOR S.J. Poulos

7


AREA EVALUATED	CONDITION
<p><u>OUTLET WORKS - OUTLET STRUCTURE AND OUTLET CHANNEL</u></p> <p>General Condition of Concrete</p> <p>Rust or Staining</p> <p>Spalling</p> <p>Erosion or Cavitation</p> <p>Visible Reinforcing</p> <p>Any Seepage or Efflorescence</p> <p>Condition at Joints</p> <p>Drain holes</p>	<p>Outlet is a penstock leading to Silver Lake in Town of Leicester, Vermont. Structure at end of 1.5-mile penstock not inspected.</p>
Channel	N/A
Loose Rock or Trees Overhanging Channel	N/A
Condition of Discharge Channel	N/A
A-7	


GEI

GEI

GEI

EI






SECTION AT JOINT
Scale 1"=10'-0"

WATER STOP

... ..




SECTION A
STEEL SECTION


... ..

SECTION D
Scale 1"=20'-0"


... ..



TYPICAL SECTION C
Scale 1"=20'-0"



SECTION B
Scale 1"=20'-0"



SECTION A
Scale 1"=20'-0"



GENERAL
SILVER

RAILWAY

SECTION D

Scale 1" = 20' 0"


1. The structure is to be built on a foundation of concrete piers and proper, bonded.

2. The structure is to be built on a foundation of concrete piers and proper, bonded.




TYPICAL SECTION C

Scale 1" = 20' 0"




SECTION B

Scale 1" = 20' 0"



SECTION A

Scale 1" = 20' 0"



GENERAL ENGINEERING DIVISION
SILVER LAKE STATION
CENTRAL VERMONT TUNNEL SERVICE

3073

DETAIL "Z"
Scale 1/4" = 1'-0"

SECTION D-D

INTAKE HEAD WALL
Scale 1/4" = 1'-0"


Note: Make connection
joint only between wall and
channel. Channel and support
by field concrete.

Notes: Channel
to be set in
concrete.

INTER-AM
ELEVATION
Scale 1/4" = 1'-0"

SECTION C-C
Scale 1/4" = 1'-0"

412-32	General Plan & Elevation
412-34	Intake & Canal
TWO NO.	
REFERENCE	
INTAKE STATION	
SUCKER BROCK OVER	
SILVER LAKE STA	
CENTRAL VERMONT PUBLIC	
NEPSCO SERVICES, INC.	
ENGINEERING DEPARTMENT	
DATE: 10-1-50	



NO. 1

20 ID of Pipe
of 20 inch cover

Model 101 C by manufacturer

3/4 in. black iron pipe fitted on
circumference of pipe

Provide good contact all around
No gap surface required

COVER DETAIL
Scale 3/4" = 1'-0"

INTAKE PIPE
Scale 3/4" = 1'-0"

20 ID of Pipe
of 20 inch cover

11


F 1

VIEW E-E
Scale 3/4" = 1'-0"

CONNECTION TO WOOD STATE PIPE
Scale 3/4" = 1'-0"

INTAKE & CONDUIT
PROPOSED
SUCKER HATCH
SILVER LAKE
CENTRAL VERMONT

NEPSCO SERVICES, INC.
ENGINEERING DEPARTMENT
Rt. 1, Box 112, Montpelier, Vt. 05602



		INTAKE & CONDUIT STRUCTURE PROPOSED FOR LINE SUCKER BROOK DIVERSION DAM SILVER LAKE CENTRAL VERMONT NEPECO SERVICES, INC. ENGINEER No. 40712		412-36
--	--	---	--	--------

COPY

H. K. BARROWS
MANUFACTURER
CONSULTING ENGINEER
6 BEACON STREET
BOSTON

Hon. Stephen S. Conant
Chairman, Vermont
Public Service Comm'n.

VERMONT PUBLIC
SERVICE COMMISSION

JUN 13 1937

June 18, 1937

RECEIVED

Mr. H. L. Durbin, Chief Engineer
Central Vermont Public Service Corp'n
Rutland, Vermont

1937
Sugar Brook Diversion

Dear Mr. Durbin:

Since my visit with you June 15th to the site of your proposed Sugar Brook Diversion Dam, I have studied the plans and given some thought to the proposed construction.

48" Outlet Pipe

I think it would be better to make this a reinforced concrete conduit rather than a 36" steel pipe. The pipe will deteriorate rather readily in the earth fill and its outside will not be accessible for inspection or painting. Moreover, it will be carrying a heavy load of earth and is likely to distort somewhat between times of filling and emptying the pipe, which will occur from time to time - thus tending to start leaks.

If the steel pipe has been ordered I think it would be well to embed it in concrete, which could be of a cross-section about 5'-6" square in outside dimensions, with some cross and longitudinal reinforcement. The concrete should project about 12" outside the 5'-6" square section should be located in about the upstream third of the dam cross-section.

If the steel pipe order can be countermanded, it can be omitted and a concrete section with suitable reinforcement used in its place.

The 30" diameter pipe should leave the pipe at a point outside the downstream slope of the dam - otherwise this may be a source of future trouble.

Mr. M. L. Durain, Chief Engr.

6-19-'37

2

Earth Section

As shown on the plans this is adequate. Whenever the foundation is of solid rock there should be a suitable concrete cutoff: a line longitudinally located about as shown on Section B of sheet 412-32 of the plans and projecting upward about 3 feet.

Spillway

I assume that the crest wall or cutoff, as well as the side walls, is to be of concrete. The length of the latter each not shown on the plans, but I assume this will be for a distance of about 70 ft. (20 ft. upstream and 50 ft. downstream from the crest wall).

I will make from time to time such further suggestions as seem advisable. Meanwhile please send me a brief progress statement about every week or 10 days, so that I can keep in touch with the work.

Yours very truly,

(Sgd.) H. E. Barrows.

c.c.

Hon. Stephen S. Cushing,
Ch. Pub. Service Comm'n.

Mr. F. H. Mason, Ch. Engr.
U. S. Public Service Corp'n.

H. K. BARROWS
MEMBER SOCIETY
CONSULTING ENGINEER
6 BEACON STREET
BOSTON

November 20, 1937

Hon. Stephen S. Cushing, Chairman
Public Service Commission
Montpelier, Vermont

No. 1998 - Sucker Brook Diversion Dam

Dear Sir:

In accordance with the order of your Commission dated June 4, 1937, I submit the following report upon the Sucker Brook Diversion Dam in the town of Salisbury, Vermont.

DESCRIPTION

The Sucker Brook Diversion Dam, at the junction of Sucker and Dutton Brooks, is located about 1/2 mile easterly from the northerly end of Silver Lake. See Fig. 1. It replaces, with a higher water level, an old concrete and rubble masonry dam which has been in use at this point for over 20 years. The drainage area at this point is about 9 square miles, of which 2.5 square miles is controlled by Sugar Hill Reservoir, completed in 1931. Water from the Sucker Brook Diversion Dam (Spillway Level El. 1306) will be fed into Silver Lake Reservoir at El. 1251 by means of a 4 ft. diameter wood stave pipe line about 1-1/2 miles long, which has been reconstructed during the present season.

From Silver Lake a pipe line takes the water to the Silver Lake Power Station of the Central Vermont Public Service Corporation located near the easterly shore of Lake Dunmore (El. 571), developing a head of about 670 ft., in use 20 years or more.

The water stored above the Sucker Brook Diversion Dam is about 1.5 mill.cu.ft. at spillway level - El. 1306.

The dam is constructed of rolled earth fill about 400 ft. long and 40 ft. in maximum height, with a 150 ft. concrete spillway, all upon a clay foundation except near the westerly end of the earth fill, where ledge rock occurs and where a 4 ft. reinforced concrete outlet conduit and gate well is located. The lower end of this conduit connects with the 4 ft. wood stave pipe line to Silver Lake.

The old masonry diversion dam lies 50 to 100 ft. upstream from the earth fill section and was left in place.

The earth embankment is 10 ft. wide at the top (El. 1312), upstream it has slopes of 1 on 2 $\frac{1}{2}$, covered with boulder riprap the full height. Downstream slope is 1 on 2, covered for some distance up with boulder riprap and the remainder loamed and seeded with grass. The fill is of borrow material obtained on the hillside west of the dam, a "hard-pan" well graded and with sufficient fines to make a relatively impervious structure. The downstream toe is well reinforced with rock fill.

The spillway, 150 ft. long at El. 1306, between concrete abutment walls with their tops at El. 1312, is formed by a vertical cutoff wall 2 ft. thick extending downward about 8 ft. into an impervious clay bottom. The easterly wall is backed up with undisturbed earth; the westerly wall, which runs downstream about 50 ft., is backed up with earth fill covered with boulder riprap. The spillway channel curves somewhat westerly and is covered with heavy boulder riprap with gravel filling, terminating in a row of heavy boulders and joining a natural gully or channel entering the bank some distance downstream from the dam.

The outlet works include a 3' x 4' gate well, a 4 ft. x 5 ft. gate, manually operated, over the upper end of the outlet conduit whose invert is at El. 1284, a rack structure & opening just upstream from the gate well, with scum racks which permit draft to about El. 1293. A 24" steel pipe between the gate well and upstream toe of the dam, invert at El. 1284, permits draft to El. 1288.

The outlet conduit is of reinforced concrete, 4 ft. high x" wide, about 100 ft. long, running to a point a little downstream from the downstream toe of the earth fill where it joins the 4 ft. wood stave pipe line, the transition being through a short length of 4 ft. diameter pipe. The upstream end of the outlet

AD-A156 889


NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS
SUCKER BROOK DAM (VT. (U) CORPS OF ENGINEERS WALTHAM MA
NEW ENGLAND DIV FEB 80

212

UNCLASSIFIED


F/G 13/13

NL



END

FILED



MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS 1963-A

conduit and the gate well are on lodge rock, the remainder in hard clay excavation, with a cutoff about 30 ft. from the gate well.

Details of the various portions of the dam and its accessories are shown on plans 412-32, 412-33 and 412-36 appended.

INVESTIGATIONS

In the Field.

June 15, 1937 Visited the work with Messrs Dargin, Belden and Burditt of the Company's staff. Work beginning - building road and developing borrow pits. Suggested that outlet pipe should be changed from a steel pipe to a reinforced concrete conduit, for better permanence and safety. This change made.

July 6, 1937 Visited the work with Messrs. Belden and Burditt. Some excavation of bottom for earth fill section. Borrow pits being developed. Excavation made for outlet conduit. Sand and stone for concrete just beginning to arrive. Cement on way. Arranged for samples of cement and sand to be sent to Boston for testing.

Aug. 9, 1937 Visited work with R.A. Burditt - Resident Engineer Flanders also on hand. Starting impervious fill cutoff. Little progress on spillway. Bottom of outlet conduit all poured and sides and top under way. Borrow pit for fill developed on side hill west of dam.

Sept. 14, 1937 Visited work with Messrs. Durgin and Burditt. Resident Engineer Flanders on hand. Earth fill approximately half in place - well compacted. Spillway - about half concrete wall in place - good impervious foundation - reinforced with steel. Conduit completed, including steel pipe for waste below dam.

Oct. 13, 1937 Visited work with Messrs. Burditt and Belden. Resident Engineer Flanders on hand. Earth fill completed. Spillway channel under way. Made suggestions as to riprap and backing up of westerly abutment wall, confirmed in detail by letter to R. A. Burditt on Oct. 16th.

Oct. 22, 1937 Visited work with Messrs. Burditt and Belden. Resident Engineer Flanders on hand. Spillway channel nearly completed, and in accordance with suggestions made by letter of Oct. 16th. Downstream slopes of earth fill about half loamed. Little further work required for completion.

Photographs of Project. Appended are a number of photographs taken at different times during construction by the Company's engineers, with descriptive notes.

Office Work. This has included a study to determine the adequacy of the spillway and its channel and a review of design. With such changes as suggested and carried out these are satisfactory.

CONCLUSIONS AND RECOMMENDATIONS

This project was designed by competent engineers and has been well carried out under the immediate direction of Resident Engineer Flanders and supervision of Mr. R. A. Burditt. The superintendent upon the work, Mr. Wm. Leighton, is a man of much experience in such work.

While the spillway and its channel are constructed upon an earth foundation, this is of clay hard-pan and the construction is adequate for these conditions.

Some wash in the natural earth channel at the end of the boulder riprap may occur as time goes on, although this is hard material with numerous boulders. Flow over the spillway will occur frequently as the storage above the dam is relatively small. The condition of the spillway channel should therefore be noted from time to time and repairs made if necessary.


This dam as constructed, in my judgment provides adequately for the public safety and its manner of construction is satisfactory.


Acknowledgments are made to the engineers of the Central Vermont Public Service Corporation for assistance and courtesies rendered.

Respectfully submitted,

Accompanied by:-

- (1) Plans: Fig. 1
412-32
412-33
412-36
- (2) 6 Photographs
during construction.





١٠٠

STATE OF VERMONT
PUBLIC SERVICE COMMISSION

No. 1298

Petition of Central Vermont
Public Service Corporation for
authority to construct a dam on
Sucker Brook, so-called, in
Salisbury, Vermont.

ORDER

WHEREAS, the Central Vermont Public Service Corporation, a corporation under the laws of Vermont engaged in the generation, manufacture and sale of electricity to the public, on the 19th day of May, 1937 filed with this Commission its petition seeking the approval of this Commission to the construction of a dam impounding more than 500,000 cubic feet of water at the junction of Dutton and Sucker Brooks in Salisbury, Vermont, and

WHEREAS, this Commission on the 4th day of June, 1937, with the approval of George D. Aiken, Governor of Vermont, designated H. K. Barrows of Boston as engineer to investigate the property, review the plans and specifications and to make such additional investigation as the Commission should deem necessary and

WHEREAS, such investigations and review have been made by said H. K. Barrows, and

WHEREAS, said H. K. Barrows on the 22nd day of November, 1937, filed with this Commission his report on the Sucker Brook Diversion Dam at the junction of Dutton Brook and Sucker Brook in Salisbury, Vermont, in which it is set forth that said dam as constructed provides adequately for the public safety and its manner of construction is satisfactory,

THEREFORE, this Commission issues its Order approving the construction of such dam in accordance with the report filed by said H. K. Barrows.

Dated at Montpelier, County of Washington, State of Vermont, this
8th day of December, A. D. 1937.

OFFICE OF CLERK
Filed: December 8, 1937

Stephen S. Connelley) Public Service
Commission
Miss Margaret) of Vermont

H. K. BARROWS
CONSULTING ENGINEER
6 BEACON STREET
BOSTON

November 27, 1939

Hon. E. B. Cornwall, Chairman
Public Service Commission
Montpelier, Vermont

No. 2102 - Sucker Brook Spillway Improvement

Dear Sir:

In accordance with the order of your Commission dated April 24, 1939, I submit the following report upon Spillway Improvement at Sucker Brook Diversion Dam in the town of Salisbury, Vermont.

Description

The Sucker Brook Diversion Dam was completed in 1937 and is fully described in my report to the Commission dated November 20, 1937.

The flood of September 1938 caused the spillway channel below the dam to be so badly washed as to necessitate the reconstruction of the channel. Bed-rock in the channel was uncovered by the wash, so that it was considered desirable to relocate the spillway on a rock foundation, and reconstruct the channel in such bed-rock. The new spillway location is at the North-East of the original spillway.

The work involves the removal of the retaining wall at the West end of the embankment and the extension of the embankment in a North-East direction about 180 ft. to the new spillway location; construction of new retaining wall and wing wall at the North-East end of embankment; placing heavy riprap on downstream side of embankment adjacent to the channel; construction of a new concrete spillway crest, with wooden flashboards; and excavation for the new channel.

The new concrete spillway is 40 ft. long at El. 1302, with 4 ft. flashboards, and there is an additional length of 20 ft. of permanent crest at El. 1306. Flashboards are designed to go out when the water level reaches El. 1307.3.

The new spillway and retaining wall are founded on solid rock and the new channel bottom is rock for some distance downstream from the spillway.

The ordinary elevation of the water surface upstream from the dam remains unchanged.

Details of the work are shown on plan 412-46, appended.

Aug. 11, 1939. Visited the work. Present, - Messrs. Harris, Belding, Belding, Whitcomb (Resident Engineer) and Merry (Contractor). Large spillway wall foundation rock uncovered and excavated to El. 1304 and O.K. Spillway wall foundation rock in part uncovered. Earth fill being placed between new spillway and earth dam.

Aug. 24, 1939. Visited the work. Present, - Messrs. Harris, Belding, Belding, Whitcomb (Resident Engineer) and Merry (Contractor). Large spillway wall foundation rock uncovered and excavated to El. 1304 and O.K. Spillway wall foundation rock in part uncovered. Earth fill being placed between new spillway and earth dam.

Aug. 24, 1939. Visited the work. Present, - Messrs. Dargin and Whitcomb (Resident Engineer). Spillway foundation rock uncovered and excavated to El. 1304 and O.K. Spillway wall foundation rock in part uncovered. Earth fill being placed between new spillway and earth dam.

Oct. 5, 1939. Visited the work. Present, - Messrs. Dargin, Belding, Whitcomb (Resident Engineer) and Merry (Contractor).

Spillway - Concrete nearly all poured - rock foundation all the way - O.K.

Spillway Wall - Complete except for 28 ft. section near middle. Rock foundation all the way - some seamy, but O.K.

plan of the dam.

5-11-17

The following items were checked: the design of the spillway to provide for stability of the spillway section and a general review of the plans. These were found to be satisfactory.

Conclusions and Recommendations

The project was designed and constructed by competent engineers and was satisfactorily carried out. The new spillway and channel are entirely in solid rock except for the North bank. Though some wash might occur here in a large flood, it would not affect the safety of the dam.

This spillway and dam as constructed, in my judgment provide adequately for the public safety.


Acknowledgments are made to the engineers of the Central Vermont Public Service Corporation for assistance and courtesies rendered.

Respectfully submitted,



Accompanied by:-

- (1) Plans 112-46
- (2) 5 Photographs




SPELWAY IMPROVEMENTS	
S. CREEK BRIDGE DIVERSION	
MAIN-5 LAMP LAKE STATION	
CENTRAL HILL DISTRICT	
NEPACCO SERVICES, INC.	612-411
FOR A LIST OF OUR PROJECTS	

340




C-8A Deteriorated concrete support for service bridge on
control tower - 11/07/79




C-8B Crack in concrete on left side of control tower - 11/07/79



C-7A Intake structure and control tower - 11/07/79



C-7B Slide gate control mechanism on top of control tower
11/07/79



C-6A Ponded water at downstream toe
of dam looking from dam crest
11/07/79




C-6B Upstream slope of dam looking left from spillway approach
channel. Note riprap - 11/07/79




C-5A Left side of downstream slope of dam looking from left abutment. Note rock cover at bottom left - 11/07/79




C-5B Right side of downstream slope of dam looking from left abutment - 11/07/79




C-4A Dam crest looking from left abutment toward right abutment
11/07/79



C-4B Downstream slope of dam near
left abutment. Note rock cover on
slope and outlet penstock just visi-
ble in background above center
11/07/79



C-3A Dam crest looking from left spillway training wall toward left abutment. Note left training wall of old spillway right of center - 11/07/79




C-3B Upstream face of dam looking from right angle point toward left abutment - 11/07/79



C-2A Dam crest looking from left spillway training wall toward right angle point. Note top of left training wall of old spillway just visible at extreme left of center - 11/07/79



C-2B Close-up of upstream end of left training wall of old spillway where it starts through dam - 11/07/79



FOLLOWING PHOTOS ARE INDEXED
ON APPENDIX D-1:

12 B
13 A
13 B

SUCKER BROOK DAM PHOTO INDEX MAP APPENDIX C-1

GORDON E. AINSWORTH & ASSOCIATES INC.

Engineers, Surveyors and Planners

20 SUGARLOAF ST. SOUTH DEERFIELD MASS. 01373




SCALE NONE

FEBRU

1980

DWG. NO. 80-119



FOLLOWING PHOTOS ARE INDEXED
ON APPENDIX D-1:

12B
13A
13B

SUCKER BROOK RESERVOIR
(ALMOST EMPTY)


SCALE - NONE

**SUCKER BROOK
PHOTO INDEX
APPENDIX C-**

GORDON E. AINSWORTH & ASSC.

Engineers, Surveyors and Plan
20 SUGARLOAF ST. SOUTH DEERFIELD

FEBRUARY 1980



APPENDIX C

PHOTOGRAPHS

Conclusions

There is no appreciable change in the stability of this dam since its construction.

Stephen H. Haybrook

STEPHEN H. HAYBROOK
HYDRAULIC ENGINEER

Public Service Commission

April 17, 1951

SN
Report No. 199

has a stone riprap cover, while the remainder of the dam is seeded with grass.

At the north-east end of the embankment is a spillway located on a ledge rock foundation. It consists of a concrete cap anchored to the bed rock. Of this, a 40 ft. length has its crest 10 ft. below the top of the dam, and a 20 ft. extension has its crest 6 ft. below the top of the dam. The 40 ft. length is fitted with 4 ft. of pin-type flashboards designed to fall with 1.3 ft. of water over them. A concrete retaining wall and wing wall protects the embankment fill.

Near the westerly end of the embankment is a 4'x3.2' reinforced concrete outlet on a rock foundation. At the upstream end is a 3'x4' gate well, and a rack structure. At the downstream end is a transition to a 4 ft. dia. wood stave pipe. The wood stave pipe continues to Silver Lake, a distance of 1.5 miles.

Comments on Inspection

From inspection, this dam appears in a good condition. It is a relatively recent structure, properly maintained.

Acknowledging H. K. Barrows' two reports on this dam, it was designed and built in a satisfactory manner. After damage by the 1938 Flood, the spillway was relocated in a more ideal position.

The embankment fill is a well graded material. There is ample spillway capacity.

The discharge channel may be subjected to erosion in flood time but the safety of the dam from such a condition would not be affected.

REPORT ON SUCKER BROOK DAM

General Data

1. Owner & Operator - Central Vermont Public Service Corp.
2. Purpose of dam - Diversion for Silver Lake hydroelectric development
3. Stream location - Sucker Brook (junction of Dutton Br.)
4. Town location - Salisbury, Vt. (south east corner)
5. Size of Pond - At maximum level the surface area is 4 acres and the volume 1,500,000 cu. ft.
6. Drainage area - Approximately 9 sq. mi. of which, 2.5 sq. mi. is regulated by Sugar Hill Dam.

Historical brief

Constructed in 1937, the dam replaces, with a larger capacity, an old concrete and rubble masonry structure. The project was approved by PSC in Case #1998, with H. K. Barrows, Consulting Engineer, designated as the Commission's engineer in the matter.

The flood of September, 1938 damaged the spillway channel. Improvements in 1939 were approved under PSC Case #2102. H. K. Barrows again acted for the Commission.


Description of the dam

Layout, dimensions and details are contained in the PSC case files on the dam. Briefly, it consists of the following:

The dam is a rolled earth embankment on a clay foundation. It is about 550 ft. in length and 40 ft. in maximum height. Its top width is 10 ft. and its upstream and downstream faces slopes, respectively, 1 on $2\frac{1}{2}$ and 1 on 2. In general, the upstream face



C-9A Path of penstock at downstream end of outlet pipe.
Note exposed penstock near center - 11/07/79



C-9B Approach channel to spillway looking from spillway
weir - 11/07/79



C-10A Spillway weir looking toward left training wall - 11/07/79



C-10B Spillway weir looking upstream from discharge channel
11/07/79



C-11A Spalling of concrete at construction joint in left training wall of spillway discharge channel - 11/07/79



C-11B Spillway discharge channel looking downstream from left training wall of spillway. Note training wall along left side of channel - 11/07/79



C-12A Undermining and deterioration of downstream end of left training wall of spillway discharge channel - 11/07/79



C-12B Vermont State Route No. 53 bridge over Sucker Brook near Lake Dunmore. Note top of powerhouse for Silver Lake Hydro-electric Development visible over left end of bridge - 11/08/79




C-13A Aerial overview of downstream hazard area along Lake Dunmore. Sucker Brook Dam is in the mountains in the background - 11/30/79




C-13B Aerial overview of downstream hazard area along Lake Dunmore. Note Vermont State Route No. 53 across center, Branbury State Park in left center and outlet to Sucker Brook in right foreground - 11/30/79

APPENDIX D
HYDRAULIC AND HYDROLOGIC COMPUTATIONS
TABLE OF CONTENTS

	<u>PAGE</u>
Drainage Area Map	D-1
Elevation - Area - Storage Computations	D-2
Stage - Area Curve	D-3
Stage - Storage Curve	D-4
Discharge Computations	
Outlet Conduit	D-5
Summary	D-6
Stage - Discharge Curve	D-7
Drainage Area Data for HEC-1 DB Program	D-8
Sugar Hill Dam	
Elevation - Area - Storage Computations	D-11
Discharge Computations	D-12
Drainage Area Routing	
Cross Sections of Subarea 3 Channel	D-13
Overtopping Analysis	
Computer Input	D-15
Computer Output - Complete	D-17
Inflow and Outflow Hydrograph Plot	D-23
Dam Failure Analysis	
Cross Sections of Downstream Channel	D-27
Profile of Downstream Channel	D-31
Prior Flow at Top of Dam	
Computer Input	D-32
Computer Output	
Summary Tables	D-34
Breach Criteria	D-36
Breach at Top of Dam	
Computer Input	D-37
Computer Output	
Breach Hydrograph Listing & Plot	D-39
Inflow and Outflow Hydrograph Plot	D-41
Summary Tables	D-42





G. E. Ainsworth Associates

20 Sugarloaf Street
S. DEERFIELD, MA 01373
Phone 665-2161

JOB SUCKER BROOK DAM

SHEET NO. _____

OF _____

CALCULATED BY CLV

DATE 1/29/80

CHECKED BY 473

DATE 5/80

SCALE 21-06-79108

ELEVATION - AREA - STORAGE COMPUTATIONS

SUCKER BROOK RESERVOIR VOLUME: COMPUTED BY PROGRAM USING METHOD OF CONIC SECTIONS $V_{12} = \frac{h}{3} (A_1 + A_2 + \sqrt{A_1 A_2})$

ELEVATION (NGVD - Ft)	AREA (acres)	V_T (acre-feet)
1280	0.02	0
1290	0.33	1
1300	2.76	15
LOWER SPILLWAY CREST → 1302*	3.0 (EST.)	21
UPPER SPILLWAY CREST → 1306*	3.51	34 = 1.481 MCF ↗
1310	4.19	49 (1.425 MCF +)
DAM CREST → 1311.2**	4.5 (EST.)	54 (1.5 MCF REPORTED)
(LOW POINT) 1320	6.67 BATHYMETRIC MAP	103

DRAINAGE AREA

AREA
(acres) (square miles)

SUGAR HILL RESERVOIR SURFACE (SUBAREA 2)
@ NORMAL POOL EL = 1768
(PHASE I REPORT FOR VT00176)

74.1 0.116

WATERSHED DIRECT TO SUGAR HILL DAM (SUBAREA 1)

1827.2 2.855
2.971

SUCKER BROOK ABOVE SUCKER BROOK DAM (SUBAREA 3)

1742.1 2.722

DUTTON BROOK ABOVE SUCKER BROOK DAM (SUBAREA 4)

3079.7 4.812

SUCKER BROOK RESERVOIR SURFACE (SUBAREA 5)

30 0.005
7.539

TOTAL DRAINAGE AREA TO SUCKER
BROOK DAM


6726.1 10.51

* FROM ENGINEERING DATA IN APPENDIX B3.

** FROM FIELD MEASUREMENTS


SUCKER BROOK DAM, SALISBURY, VERMONT

STAGE - AREA



SUCKER BROOK DAM, SALISBURY, VERMONT

STAGE - STORAGE



G. E. Ainsworth Associates

20 Sugarloaf Street
S. DEERFIELD, MA 01373
Phone 665-2161

JOB SUCKER BROOK DAM

SHEET NO. _____ OF _____

CALCULATED BY CLV DATE 1/29/80

CHECKED BY TPB DATE 5/80

SCALE 21-06-79108

DISCHARGE COMPUTATIONS - SUCKER BROOK DAM

OUTLET CONDUIT

(OUTLET CONTROLLED DUE TO LENGTH & LOW HEAD)
SEE INLET CONTROL CHECK BELOW.

$L = 1.5 \text{ miles} = 7920'$ LENGTH OF PENSTOCK TO SILVER LAKE


$D = 4'$ DIAMETER OUTLET

$n = 0.013$ (ASSUMED)

$K_{\text{entrance}} = 1.0$ (ASSUMED)

$K_{\text{exit}} = 0.5$ (ASSUMED)

$H = 23'$ MINIMUM HEIGHT DIFFERENCE BETWEEN WATER SURFACE IN
SUCKER BROOK RESERVOIR (EL 1293 @ INTAKE INVERT) AND OUTLET
AT SILVER LAKE (EL 1270)



FOR OUTLET CONTROL:

(DERIVED FROM APPLICATION OF BERNOULLI'S EQUATION
USING MANNING'S EQUATION FOR FRICTION LOSS)

$$Q = \left[\frac{S_{ws}}{\frac{K_{\text{entrance}} + K_{\text{exit}}}{2gA^2L} + \frac{n^2}{2.21A^2R^{4/3}}} \right]^{1/2}$$

$$S_{ws} = H/L$$

$$A = \frac{\pi D^2}{4} = 12.566 \text{ SQ. FT.}$$

$$R = A/P = 1.0'$$

	WATER SURFACE ELEVATION (NGVD - ft.)	H (ft.)	Q (cfs)	CHECK Q INLET CONTROL (cfs)		WATER SURFACE ELEVATION (NGVD - ft.)	H (ft.)	Q (cfs)	CHECK Q INLET CONTROL (cfs)
INTAKE INVERT →	1293	23	0			1308	38	97.7	
	1293.1	23.1	76.2			1309	39	99.0	
	1295	25	79.2			1310	40	100.2	
	1300	30	86.8			1311	41	101.5	
LOWER SPILLWAY CREST →	1302	32	89.6	(160)	DAM CREST →	1311.2	41.2	101.7	(258)
	1303	33	91.0	say 90		1312	42	102.7	say 100
	1304	34	92.4			1313	43	103.9	
	1305	35	93.7			1314	44	105.1	(277)
UPPER SPILLWAY CREST →	1306	36	95.1	(201)		1315	45	106.3	
	1307	37	96.4	say 95		1316	46	107.5	
						1320	50	112.0	

$$A = 12.566 \text{ SF } (4' \phi) \text{ OR } 12.6 \text{ SF } (3'-2" \times 4')$$

$$C = 0.6$$

CHECK INLET CONTROL

$$Q = CA \sqrt{2gh}$$

$$= 60.5 (h)^{1/2}$$



G. E. Ainsworth Associates

20 Sugarloaf Street
S. DEERFIELD, MA 01373
Phone 665-2161

JOB

SUCKER BROOK DAM

SHEET NO.

OF

CALCULATED BY

ELV

DATE

1/29/80

CHECKED BY

JPB

DATE

5/80

SCALE

21-06-79108

DISCHARGE COMPUTATIONS - SUCKER BROOK DAMDAM APPURTENANCE

ELEVATION (NGVD)

SIZE

LOWER CHUTE SPILLWAY (LS)*

CREST EL = 1302

40' CREST LENGTH

UPPER CHUTE SPILLWAY (US)*
(MODELED AS BROAD-CRESTED WEIR BECAUSE
OF APPROACH AND DISCHARGE CHANNEL BOTTOMS)

CREST EL = 1306

20' CREST LENGTH

DAM**

CREST EL = 1311.2
(LOW POINT, NON-LEVEL)600' CREST LENGTH
W/O SPILLWAY

OUTLET CONDUIT

INTAKE EL = 1293

4' DIAMETER

	ELEVATION (NGVD)	Q_{spill} (cfs)	H_{LS} (feet)	H_{US} (feet)	H_{DAM} (feet)	Q_{OUTLET} (cfs)	Q_{LS}^* (cfs)	Q_{US}^* (cfs)	Q_{DAM}^{**} (cfs)	Q_T (cfs)
TAKE VERT →	1293	0	0	0	0	0	0	0	0	0
	1293.1	0	0	0	0	76.2	0	0	0	76
	1295	0	0	0	0	79.2	0	0	0	79
	1300	0	0	0	0	86.8	0	0	0	87
OWER ILLWAY REST →	1302	0	0	0	0	89.6	0	0	0	90
	1303	124	1	0	0	91.0	123.5	0	0	214
	1304	349	2	0	0	92.4	349.3	0	0 (442)	437
	1305	642	3	0	0	93.7	641.6	0	0	736
PER ILLWAY EST →	1306	988	4	0	0	95.1	987.8	0	0	1083
	1307	1442	5	1	0	96.4	1380.5	61.7	0	1538
	1308	1989	6	2	0	97.7	1814.8	174.6	0	2087
	1309	2618	7	3	0	99.0	2286.9	330.8	0	2717
	1310	3288	8	4	0	100.2	2794.0	493.9	0	3388
	1311	4024	9	5	0	101.5	3334.0	690.3	0	4126
EST →	1311.2	4182	9.2	5.2	0	101.7	3450.2	732.1 (730)	0	4284 (4280)
	1312	4812	10	6	0.8	102.7	3904.8	907.4	130	5045
	1313	5648					4504.9	1143.4		
	1314	6530	12	8	2.8	105.1	5133.0	1397.0	4399	11,034
	1315	7455					5787.8	1667.0		
	1316	8421	14	10	4.8	107.5	6468.3	1952.4	13664	22192
	1320	12,664					9430.0	3234.1		

* FOR FLOW OVER SPILLWAY:

 $Q = 3.087 L H^{1.5}$ (FORMULA FOR CRITICAL FLOW OVER BROAD-CRESTED WEIR, REFERENCE 9)

** FOR FLOW OVER DAM:

CALCULATED W/ HEC-1 DB PROGRAM FOR FLOW OVER NON-LEVEL DAM CREST.

CROSS SECTION COORDINATES--STA=ELEV,STA=ELFV--ETC
 6.00 1340.00 70.00 1320.00 100.00 1300.00 110.00 1297.00 115.00 1297.00
 125.00 1307.00 370.00 1300.00 500.00 1340.00

SUB-AREA RUNOFF COMPUTATION

SUBAREA 3 RUNOFF COMPUTATION

ISTEQ ICCOR JECOR IIAPE JPLI JPRT IMAPE IMAPE IMAUTO
 54-3 0 0 0 0 0 0 0 0

HYDROGRAPH DATA

INPCS IUPC IAREA SNAP TRSDA TRSFC RATIO ISHOW ISAMP LOCAL
 1 1 2.72 0.00 10.51 0.00 0.000 0 1 0

ISICP DATA

CPFI PMS PC P2 P24 P28 P72 R94
 0.00 17.50 111.00 123.00 122.00 0.00 0.00 0.00

TRSEC COMPUTED BY THE PROGRAM IS 6402

LOSS DATA

LSOPT STARKS LTRK RTRC ERAIN STARKS RTICK STRIL CASTL ALSXK RTIMP
 0 0.00 0.00 1.00 0.00 0.00 2.00 1.00 1.00 0.00 0.00 0.00

UNIT HYDROGRAPH DATA

TP= 2.00 CP=0.63 NTA= 0

RECESSION DATA

SIRGE -0.00 RECES= 0.00 RIJORE 1.00

UNIT HYDROGRAPHIC END-OF-PERIOD REGIMES, LAGE= 2.00 HOLES, CP= 0.62 VCL= 0.91

100	115	120	125	130	135	140	145	150	155	160	165	170	175	180	185	190	195	200	205	210	215	220	225	230	235	240	245	250	255	260	265	270	275	280	285	290	295	300	305	310	315	320	325	330	335	340	345	350	355	360	365	370	375	380	385	390	395	400	405	410	415	420	425	430	435	440	445	450	455	460	465	470	475	480	485	490	495	500	505	510	515	520	525	530	535	540	545	550	555	560	565	570	575	580	585	590	595	600	605	610	615	620	625	630	635	640	645	650	655	660	665	670	675	680	685	690	695	700	705	710	715	720	725	730	735	740	745	750	755	760	765	770	775	780	785	790	795	800	805	810	815	820	825	830	835	840	845	850	855	860	865	870	875	880	885	890	895	900	905	910	915	920	925	930	935	940	945	950	955	960	965	970	975	980	985	990	995	1000
-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	------

END-OF-PERIOD FLUX

PCADA PERIOD PALE EACS LOSS CORR C PCADA PERIOD PALE EACS LOSS CORR C
 SUM 10.52 15.90 2.62 203637.
 (-470311.804311.67311.559218)

SUB-AREA RUNOFF COMPUTATION

SUBAREA 4 RUNOFF COMPUTATION

ISTEQ ICCOR JECOR IIAPE JPLI JPRT IMAPE IMAPE IMAUTO
 54-4 0 0 0 0 0 0 0 0

HYDROGRAPH DATA

INPCS IUPC IAREA SNAP TRSDA TRSFC RATIO ISHOW ISAMP LOCAL
 1 1 4.01 0.00 10.51 0.00 0.000 0 1 0

00.0A HP.MN PERIOD RAIN EXCS LOSS COMP Q 00.0A HP.MN PERIOD RAIN EXCS LOSS COMP Q
 SUM 18.52 15.50 2.62 2085.1
 (470.3) (404.3) (67.3) (8738.03)

SUB-AREA RUNOFF COMPUTATION

SUBAREA 2 RUNOFF COMPUTATION (SUGAR HILL RESERVOIR)

ISTAO	ICOMP	IECON	ITAE	JPLT	JPER	INAME	ISTACE	IAUTO
SA-2	0	0	0	0	0	1	0	0

HYDROGRAPH DATA

INPDS	INUC	IAREA	SAF	TESO	TESC	RATC	ISLO	ISAME	LOCAL
1	-1	0.12	0.00	10.51	0.00	0.00	0	1	0

PRECIP DATA

SPEE	PMS	R6	P12	P24	P48	P72	P96
0.00	17.50	111.00	121.00	122.00	0.00	0.00	0.00

INPSEC COMPUTED BY THE PROGRAM IS 0.862

LOSS DATA

LRPT	STKR	RTOL	ERAIN	STKRS	RTOK	STRTL	CNSTL	ALMY	RTIMP
0	0.00	0.00	0.00	0.00	1.00	0.00	0.00	0.00	0.00

RECESSION DATA

STRTC	-4.00	GRCSVE	0.00	RTICK	1.00
-------	-------	--------	------	-------	------

END-OF-PERIOD FLOW

00.0A	HP.MN	PERIOD	RAIN	EXCS	LOSS	COMP Q	00.0A	HP.MN	PERIOD	RAIN	EXCS	LOSS	COMP Q
SUM	13.52	18.52	0.00	0.00	0.00	16754.0							
			(415.31)	(470.31)	(0.31)	(874.82)							

COMBINE HYDROGRAPHS

COMBINING HYDROGRAPHS 1,2

ISTAO	ICOMP	IECON	ITAE	JPLT	JPER	INAME	ISTACE	IAUTO
SA-2C	2	0	0	0	0	1	0	0

HYDROGRAPH ROUTING

ROUTING FLOWS THROUGH RESERVOIR 1 (SUGAR HILL RESERVOIR)

ISTAO	ICOMP	IECON	ITAE	JPLT	JPER	INAME	ISTACE	IAUTO
RES1	1	0	0	0	0	1	0	0

ROUTING DATA

GLSS	CLOS	AVG	IRCS	ISAF	IPPT	IPWP	LSTR
0.00	0.00	0.00	1	1	0	0	0

INSTPS	INSTL	LAC	AMSK	Y	ICK	STORA	ISPRAT
1	0	0	0.00	0.00	0.00	-1768.0	0

SURFACE AREA	0.0	2.0	7.0	15.0	21.0	30.0	38.0	45.0	58.0	67.0
	74.0	76.0	77.0	78.0	81.0	82.0	103.0			

.....
 FLOOD HYDROGRAPH PACKAGE (HEC-1)
 DAY SAFETY VERSION JULY 1978
 LAST MODIFICATION 26 FEB 79

JOH DATE: 9/15/80
 TIME: 8:56 AM

NO JOB INSPECTION CONTRACT: DACW33-80-C-0012 SPOT1
 AT: 00212 SICKER BRICK DAM, 21-06-75108
 OVERFLOWING - TEST FLOOD = HALF EPE

JOB SPECIFICATION
 NO NAME NMIN ICAY JWR JMLR MEIRC JFLI JPRI NSTAN
 100 C 5 JOECP DAT LROPT TRACE 0 0 0 0 0
 5 0 0 0 0 0

MULTI-PLAN ANALYSIS TO BE PERFORMED
 NPLANE = 1 NPTIO = 1 LPTIO = 1

RIIOSE = 0.50

SUB-AREA PULOFF COMPUTATION

SUBAREA 1 PULOFF COMPUTATION

ISTAO ICCD JECCH ITAPE JPLI JPRI INAME ISIAFE IAUIC
 SA-1 C 0 0 0 0 0 1 0 0

HYDROGRAPH DATA

INVOG IUVI TAPEA SIAF TSCA TESSC RATIO ISMOA ISAFE LOCAL
 1 1 2.85 0.00 10.51 0.00 0.000 0 1 0
 SPFE PMS R6 R12 R24 R36 R72 R96
 0.00 17.50 111.00 123.00 132.00 0.00 0.00 0.00
 TSSFC COMPUTED BY THE PROGRAM IS 0.002

PRECIP DATA

LOSS DATA

LROPI STKR CLMR PILOL EPAL SIPS RIICK SIRT CASIL ALSHY RIIME
 0 0.00 0.00 1.00 0.00 0.00 1.00 1.00 0.10 0.00 0.00

UNIT HYDROGRAPH DATA

7E 3.20 CPECA3 NIAE 0

RECESSION DATA

SIRIO = -4.00 SECSE = 0.00 RIICK = 1.00

UNIT HYDROGRAPH END-OF-PERIOD ORIGINATES LAGE 3.20 HOURS, CP = 0.63 VCL = 0.89

2	5	13	21	30	40	51	63	75	87
156	114	127	140	154	171	185	200	216	231
246	261	276	290	304	318	333	348	362	376
356	367	371	374	376	377	377	375	372	368
349	340	331	321	311	302	293	284	275	266
273	272	267	264	259	254	249	244	239	234
211	206	199	194	188	182	176	170	164	158
156	150	147	142	136	130	124	118	112	106
100	117	113	110	107	103	99	95	91	87
80	88	87	85	83	81	79	76	72	69

4 NED CAN INSPECTION CONTRACT: OACUS3-80-C-0012 SB071

5 VI_00212-2-2004-4-0000-21-00-0108

6 OVERLAPPING - TEST FLOOD = HALF PVE

286

287

288

289

290

291

292

293

294

295

296

297

298

299

300

301

302

303

304

305

306

307

308

309

310

311

312

313

314

315

316

317

318

319

320

321

322

323

324

325

326

327

328

329

330

331

332

333

334

335

336

337

338

339

340

341

342

343

344

345

346

347

348

349

350

351

352

353

354

355

356

357

358

359

360

361

362



363

364

365

GORDON E. AINSWORTH
& ASSOCIATES, INC.
20 Sugarloaf Street
SOUTH DEERFIELD, MASSACHUSETTS 01373
(413) 665-2161

JOB SUCKER BROOK DAM
SHEET NO. _____ OF _____
CALCULATED BY ELV DATE 2/1/80
CHECKED BY JPR DATE 5/80
SCALE 21-06-79108



GORDON E. AINSWORTH
& ASSOCIATES, INC.
20 Sugarloaf Street
SOUTH DEERFIELD, MASSACHUSETTS 01373
(413) 665-2161

JOB SUCKER BROOK DAM

SHEET NO. _____ OF _____

CALCULATED BY ELV DATE 2/1/80

CHECKED BY PPB DATE 5/80


SCALE 2-06-79108

STA 7+00

(LOOKING DOWNSTREAM)

n CHANNEL = 0.03

n OVERBANK = 0.04




STA 50+00

(LOOKING DOWNSTREAM)

n CHANNEL = 0.03

n OVERBANK = 0.04



G. E. Ainsworth Associates

20 Sugarloaf Street
S. DEERFIELD, MA 01373
Phone 665-2161

JOB SUCKER BROOK DAM

SHEET NO. _____ OF _____

CALCULATED BY ELV DATE 1/25/80

CHECKED BY TPB DATE 2/80

SCALE 21-06-79106

DISCHARGE COMPUTATIONS - SUGAR HILL DAM

DAM APPURTENANCE

ELEVATION (NGVD)

SIZE

SPILLWAY

CREST EL. = 1768

150' TOTAL LENGTH W/
A 100' + A 50' WEIR
CREST

DAM

CREST EL. = 1771.5
(LOW POINT, NON-LEVEL)

700' CREST LENGTH
W/O SPILLWAY

OUTLET CONDUIT

INVERT IN EL. = 1707

4'x4' BOX CULVERT
W/ VARIOUS CONTROLS

FOR FLOW OVER SPILLWAY ONLY: $Q = 3.087 L H^{1.5}$

(FORMULA FOR CRITICAL FLOW OVER A BROAD-CRESTED WEIR.
INPUTED INTO HEC-1 DB COMPUTER PROGRAM FOR DISCHARGE
COMPUTATIONS. REFERENCE 9)

ELEVATION (NGVD)	H _{SPILLWAY} (feet)	H _{DAM} (feet)	Q _{SPILLWAY} (cfs)	Q _{DAM} [*] (cfs)	Q _{OUTLET WORKS} (cfs)	Q _T (cfs)
SPILLWAY CREST → 1768	0	0	0	0	0	0
1769	1	0	463	0	ALL OUTLETS ASSUMED CLOSED ↓	463
1770	2	0	1310	0		1310
1771	3	0	2406	0		2406
DAM CREST → 1771.5	3.5	0.5	3032	0		3032
1772	4	1.5	3704	159		3863
1773	5	2.5	5177	2262		7439
1774	6	3.5	6805	5761		12566
1775	7	4.5	8576	10446	0	19022

* CALCULATED W/ HEC-1 DB PROGRAM FOR FLOW OVER NON-LEVEL
DAM CREST.

G. E. Ainsworth Associates

20 Sugarloaf Street
S. DEERFIELD, MA 01373
Phone 665-2161

JOB SUCKER BROOK DAM

SHEET NO. _____

OF _____

CALCULATED BY ELV

DATE 1/25/80

CHECKED BY JPB

DATE 2/80

SCALE 21-06-79106

ELEVATION - AREA - STORAGE COMPUTATIONS

SUGAR HILL

RESERVOIR VOLUME: COMPUTED BY PROGRAM USING METHOD
OF CONIC SECTIONS: $\Delta V_{12} = \frac{h}{3} (A_1 + A_2 + \sqrt{A_1 A_2})$

ELEVATION (NGVD - ft.)*	AREA *** (acres)	V _T ** (acre-feet)
1717	0	0
1723	2.0	4
1728	7.3	26
1733	14.8	80
1738	21.2	170
1743	30.2	297
1748	37.6	467
1753	45.4	674
1758	57.5	930
1763	66.5	1240
SPILLWAY CREST → 1768	74.1	1591
1769	75.8	1666
1770	77.4	1743
1771	79.1	1821
DAM CREST → 1771.5	79.9 EST.	1861
1772	80.7	1901
1773	82.4	1983
1780	102.7	2629

* APPLICATION REPORTS AND PLANS SUBMITTED IN 1930'S
BY CENTRAL VERMONT PUBLIC SERVICE CORPORATION TO THE
VERMONT PUBLIC SERVICE COMMISSION UTILIZE AN ARBITRARY
DATUM. NGVD ELEVATIONS ARE 1,613' HIGHER THAN
THIS ARBITRARY DATUM.

** COMPUTED BY HEC-1 DB COMPUTER PROGRAM.

*** STAGE - AREA DATA FROM FILES OF VERMONT DAM SAFETY ENGINEER
(SEE PHASE I REPORT FOR SUGAR HILL DAM, VT00176)

G. E. Ainsworth Associates

20 Sugarloaf Street
S. DEERFIELD, MA 01373
Phone 665-2161

JOB

SUCKER BROOK DAM

SHEET NO.

OF

CALCULATED BY

CLV

DATE

1/29/80

CHECKED BY

APB

DATE

5/80

SCALE

21-06-79/08

DRAINAGE AREA DATA FOR HEC-1 DB MODEL

SUBAREA 5: SUCKER BROOK
RESERVOIR SURFACE, AREA = 0.005 SQUARE MILES (3.0 ACRES)

LOSS RATES: NONE BECAUSE RAINFALL = RUNOFF FOR WATER SURFACE

UNIT HYDROGRAPH PARAMETERS:

FOR U.H. W/5 MINUTE DURATION + 1" RAIN

$$\bar{Q} = \frac{A(1")}{*} = \frac{0.005 \text{ mi}^2 (1")}{5 \text{ minutes}} \left(\frac{43560 \text{ sq. ft.}}{1 \text{ acre}} \right) \left(\frac{1'}{12"} \right) \left(\frac{1 \text{ minute}}{60 \text{ seconds}} \right) \left(\frac{640 \text{ acres}}{1 \text{ mi}^2} \right)$$

$$\bar{Q} = 39 \text{ cfs (SINCE NO LOSS RATE)}$$

DRAINAGE AREA DATA FOR HEC-1DB MODELSUBAREA 3: SUCKER BROOK ABOVE SUCKER BROOK DAM, AREA = 2.722 SQ. MI.

LOSS RATES: 1.0" - INITIALLY, 0.1"/HOUR - CONSTANT LOSS RATE

UNIT HYDROGRAPH PARAMETERS: USE SNYDER METHOD

A = DRAINAGE AREA = 2.722 SQUARE MILES

L = LENGTH OF MAIN WATERCOURSE TO UPSTREAM LIMIT OF
DRAINAGE AREA = 2.70 MILES L_{CA} = LENGTH OF MAIN WATERCOURSE TO POINT OPPOSITE THE
CENTROID OF THE DRAINAGE AREA = 1.25 MILES C_x = SNYDER'S BASIN COEFFICIENT = 2.0 ASSUMED AVERAGE C_p = SNYDER'S PEAKING COEFFICIENT = 0.625 ASSUMED AVERAGE t_p = STANDARD LAG IN HOURS = $C_x (LL_{CA})^{0.3} = 2.9$ HOURS \therefore USE $t_p = 2.9$ HOURSSUBAREA 4: DUTTON BROOK ABOVE SUCKER BROOK DAM, AREA = 4.812 SQ. MI.

LOSS RATES: 1.0" - INITIALLY, 0.1"/HOUR - CONSTANT LOSS RATE

UNIT HYDROGRAPH PARAMETERS: USE SNYDER METHOD

A = DRAINAGE AREA = 4.812 SQUARE MILES

L = LENGTH OF MAIN WATERCOURSE TO UPSTREAM LIMIT OF
DRAINAGE AREA = 3.40 MILES L_{CA} = LENGTH OF MAIN WATERCOURSE TO POINT OPPOSITE THE
CENTROID OF THE DRAINAGE AREA = 2.10 MILES C_x = SNYDER'S BASIN COEFFICIENT = 2.0 ASSUMED AVERAGE C_p = SNYDER'S PEAKING COEFFICIENT = 0.625 ASSUMED AVERAGE t_p = STANDARD LAG IN HOURS = $C_x (LL_{CA})^{0.3} = 3.6$ HOURS \therefore USE $t_p = 3.6$ HOURS

DRAINAGE AREA DATA FOR HEC-1 DB MODEL

SUBAREA 1 : AREA TRIBUTARY DIRECTLY TO SUGAR HILL RESERVOIR
AREA = 2.855 SQUARE MILES

LOSS RATES: 1.0" - INITIALLY
0.1"/HOUR - CONSTANT LOSS RATE

UNIT HYDROGRAPH PARAMETERS : USE SNYDER METHOD

A = DRAINAGE AREA = 2.855 SQUARE MILES

L = LENGTH OF MAIN WATERCOURSE TO UPSTREAM LIMIT OF
DRAINAGE AREA = 2.75 MILES

L_{CA} = LENGTH OF MAIN WATERCOURSE TO POINT OPPOSITE THE
CENTROID OF THE DRAINAGE AREA = 1.75 MILES

C_s = SNYDER'S BASIN COEFFICIENT = 2.0 ASSUMED AVERAGE

C_p = SNYDER'S PEAKING COEFFICIENT = 0.625 ASSUMED AVERAGE

t_p = STANDARD LAG IN HOURS = $C_s (LL_{CA})^{0.3} = 3.2$ HOURS

\therefore USE $t_p = 3.2$ HOURS

SUBAREA 2 : SUGAR HILL
RESERVOIR SURFACE, AREA = 0.116 SQUARE MILES (74.1 ACRES)

LOSS RATES : NONE BECAUSE RAINFALL = RUNOFF FOR WATER SURFACE

UNIT HYDROGRAPH PARAMETERS :


FOR U.H. W/ 5 MINUTE DURATION + 1" RAIN

$$\bar{Q} = \frac{A(1")}{t} = \frac{.116 \text{ mi}^2 (1")}{5 \text{ minutes}} \left(\frac{43560 \text{ SQ. FT.}}{1 \text{ acre}} \right) \left(\frac{1'}{12"} \right) \left(\frac{1 \text{ minute}}{60 \text{ seconds}} \right) \left(\frac{640 \text{ acres}}{1 \text{ mi}^2} \right)$$

$$\bar{Q} = 898 \text{ cfs (SINCE NO LOSS RATE)}$$

SUCKER BROOK DAM, SALISBURY, VERMONT

STAGE - DISCHARGE



COMBINING HYLCGRAPHPS RESI. 3.4,5

ISIAQ	ICOMP	JECCK	IIAPF	JPLY	JPRI	INAME	ISIAQE	JAUTO
2345C	4	0	0	0	0	1	5	0

HYDROGRAPH ROUTING

...ING FLOWS THROUGH ENOUGH PRESSURE ? (SHOCKS CAN BE PRESERVED)

ISIA	ICMP	IECH	IYAP	JPLI	JPEL	INAM	ISTACE	JAUTO
253H	1	0	0	2	0	1	0	0

COUNTING DATA				
CLASS	AVC	REFS	ISAME	DATE
00000				1991
00000				1991

[illegible]

MSIPS	MSICL	LAG	AMSMM	X	TCM	SIORA	ISBRAT
1	0	0	0.000	0.220	0.000	-1302	-1

STAGE	1293.00	1295.10	1297.00	1300.00	1302.00	1303.00	1305.00	1306.00
STAGE	1293.00	1295.10	1297.00	1300.00	1302.00	1303.00	1305.00	1306.00

1379.00	1379.00	1311.00	1312.00	1313.00	1314.00	1315.00	1320.00
---------	---------	---------	---------	---------	---------	---------	---------

615.	5.00	76.00	79.00	87.00	95.00	214.00	427.00	736.00	1053.00
2567.00	2717.00	3348.00	4126.00	4915.00	5752.00	6639.00	7561.00	8577.00	9699.00

SURFACE AREA =	0.	1.	4.	7.

CAP: CITY=	0.	1.	15.	34.	49.	103.

15.4115	1230	1550	1300	1306	1317	1320
---------	------	------	------	------	------	------

CPFL	SPFLD	CCOV	FYPR	FLEV	COOL	CARCA	FVPL
------	-------	------	------	------	------	-------	------

[illegible]

CAM CAYE

TCPEL CQD FXFD DAWID
1311.2 C.D C.D

126 126 600

1311.9	1312.2	1313.2	1320.0
--------	--------	--------	--------

ST. LOUIS, MO. 1942

16.55197.
 *QVF.

STATION RES2

INFLOW (I), OUTFLOW (O) AND OBSERVED FLOW (O)

0. 1000. 2000. 3000. 4000. 5000. 6000. 7000. 8000. 0. 0. 0. 0.

16.75197.
 16.40200.
 16.40201.
 16.40202.
 16.40203.
 16.40204.
 16.40205.
 16.40206.
 16.40207.
 16.40208.
 16.40209.
 16.40210.
 16.40211.
 16.40212.
 16.40213.
 16.40214.
 16.40215.
 16.40216.
 16.40217.
 16.40218.
 16.40219.
 16.40220.
 16.40221.
 16.40222.
 16.40223.
 16.40224.
 16.40225.
 16.40226.
 16.40227.
 16.40228.
 16.40229.
 16.40230.
 16.40231.
 16.40232.
 16.40233.
 16.40234.
 16.40235.
 16.40236.
 16.40237.
 16.40238.
 16.40239.
 16.40240.
 16.40241.
 16.40242.
 16.40243.
 16.40244.
 16.40245.
 16.40246.
 16.40247.
 16.40248.
 16.40249.
 16.40250.
 16.40251.
 16.40252.
 16.40253.
 16.40254.
 16.40255.
 16.40256.
 16.40257.
 16.40258.
 16.40259.
 16.40260.
 16.40261.
 16.40262.
 16.40263.
 16.40264.
 16.40265.
 16.40266.
 16.40267.
 16.40268.
 16.40269.
 16.40270.
 16.40271.
 16.40272.
 16.40273.
 16.40274.
 16.40275.
 16.40276.
 16.40277.
 16.40278.
 16.40279.
 16.40280.
 16.40281.
 16.40282.
 16.40283.
 16.40284.
 16.40285.
 16.40286.
 16.40287.
 16.40288.
 16.40289.
 16.40290.
 16.40291.
 16.40292.
 16.40293.
 16.40294.
 16.40295.
 16.40296.
 16.40297.
 16.40298.
 16.40299.
 16.40300.

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
 AREA IN SQUARE FEET (SQUARE KILOMETERS)

RATIOS APPLIED TO FLOWS

PLAN RATIO 1
 0.50

HYDROGRAPH AT SA-1 2.55 1 2153
 (7.10) (62.50)

HYDROGRAPH AT SA-2 0.12 1 799
 (0.30) (21.02)

2 COMBINED SA-2C 2.97 1 2158
 (7.69) (61.12)

ROUTED TO RES1 2.97 1 2017
 (7.69) (57.12)

ROUTED TO 7.00 2.97 1 2017
 (7.69) (57.12)

ROUTED TO 50.00 2.97 1 2010
 (7.69) (56.02)

ROUTED TO 100.00 2.97 1 2009
 (7.69) (56.89)

ROUTED TO 140.00 2.97 1 2007
 (7.69) (56.03)

HYDROGRAPH AT SA-3 2.72 1 2172
 (7.69) (61.50)

HYDROGRAPH AT SA-4 4.01 1 3394
 (12.44) (94.73)

HYDROGRAPH AT SA-5 0.00 1 32
 (0.01) (0.92)

4 COMBINED -23450 10.51 1 7290
 (27.22) (266.42)

ROUTED TO RES2 10.51 1 7290
 (27.22) (266.42)

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1

| | | |
|---------------|----------------|------------|
| INITIAL VALUE | SPILLWAY CREST | TOP OF DAM |
| 1768.00 | 1768.00 | 1771.50 |
| 1591. | 1591. | 1861. |
| 0. | 0. | 3032. |

| | |
|-----------|---------|
| ELEVATION | OUTFLOW |
| 1591. | 0. |

| RATIO | MAXIMUM | MINIMUM | MAXIMUM | MINIMUM | DURATION | TIME OF | TIME OF |
|-------|----------|---------|---------|----------|----------|-------------|---------|
| OF | DEPTH | STORAGE | OUTFLOW | OVER TOP | HOURS | MAX OUTFLOW | FAILURE |
| PSE | OVER DAM | AD-ET | CFS | HOURS | HOURS | HOURS | HOURS |
| 0.50 | 1770.07 | 0.00 | 1705. | 2017. | 0.00 | 15.33 | 0.50 |

PLAN 1 STATION 7+00

| RATIO | MAXIMUM | MINIMUM | MAXIMUM | MINIMUM | TIME |
|-------|----------|---------|---------|----------|-------|
| OF | DEPTH | STORAGE | OUTFLOW | OVER TOP | HOURS |
| PSE | OVER DAM | AD-ET | CFS | HOURS | HOURS |
| 0.50 | 1770.07 | 0.00 | 1705. | 2017. | 15.42 |

PLAN 1 STATION 50+00

| RATIO | MAXIMUM | MINIMUM | MAXIMUM | MINIMUM | TIME |
|-------|----------|---------|---------|----------|-------|
| OF | DEPTH | STORAGE | OUTFLOW | OVER TOP | HOURS |
| PSE | OVER DAM | AD-ET | CFS | HOURS | HOURS |
| 0.50 | 1770.07 | 0.00 | 1705. | 2017. | 15.58 |

PLAN 1 STATION 100+00

| RATIO | MAXIMUM | MINIMUM | MAXIMUM | MINIMUM | TIME |
|-------|----------|---------|---------|----------|-------|
| OF | DEPTH | STORAGE | OUTFLOW | OVER TOP | HOURS |
| PSE | OVER DAM | AD-ET | CFS | HOURS | HOURS |
| 0.50 | 1770.07 | 0.00 | 1705. | 2017. | 15.67 |

PLAN 1 STATION 140+00

| RATIO | MAXIMUM | MINIMUM | MAXIMUM | MINIMUM | TIME |
|-------|----------|---------|---------|----------|-------|
| OF | DEPTH | STORAGE | OUTFLOW | OVER TOP | HOURS |
| PSE | OVER DAM | AD-ET | CFS | HOURS | HOURS |
| 0.50 | 1770.07 | 0.00 | 1705. | 2017. | 15.75 |

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1

| | | | |
|-----------|---------------|----------------|------------|
| ELEVATION | INITIAL VALUE | SPILLWAY CREST | TOP OF DAM |
| STORAGE | 1302.00 | 1302.00 | 1311.20 |
| OUTFLOW | 21. | 21. | 54. |
| | 90. | 90. | 4264. |

| | | | | | | |
|-------|-----------|----------|---------|----------|----------|-------------|
| RATIO | MAXIMUM | MAXIMUM | MAXIMUM | DURATION | TIME OF | TIME OF |
| OF | RESERVOIR | DEPTH | STORAGE | OVERFLOW | OVER TOP | MAX OUTFLOW |
| P.F. | MAXIMUM | OVER DAM | AC-ET | CFS | HOURS | HOURS |
| 1.50 | 1311.05 | 1.25 | 61. | 7289. | 5.00 | 19.00 |
| | | | | | | 0.00 |

G. E. Ainsworth Associates

20 Sugarloaf Street
S. DEERFIELD, MA 01373
Phone 665-2161

JOB SUCKER BROOK DAM

SHEET NO. _____ OF _____

CALCULATED BY CLV

DATE 2/1/80

CHECKED BY GPB

DATE 5/80

SCALE 21-06-79108


STA 3+00 SUCKER BROOK

STA 147+00 SUGAR HILL

(700 FEET DOWNSTREAM
OF SUCKER BROOK DAM)

n CHANNEL = 0.03

n OVBANK = 0.04



THIS SECTION ONLY USED FOR PRIOR FLOW.
NOT USED FOR BREACH.

GORDON E. AINSWORTH
& ASSOCIATES, INC.
20 Sugarloaf Street
SOUTH DEERFIELD, MASSACHUSETTS 01373
(413) 665-2161

JOB SUCKER BROOK DAM

SHEET NO. _____

OF _____



CALCULATED BY ELV

DATE 2/1/80

CHECKED BY QMB

DATE 5/30

SCALE 21-06-79108



GORDON E. AINSWORTH
& ASSOCIATES, INC.
20 Sugarloaf Street
SOUTH DEERFIELD, MASSACHUSETTS 01373
(413) 665-2161

JOB SUCKER BROOK DAM

SHEET NO. _____

OF _____



CALCULATED BY ELV

DATE 2/1/80

CHECKED BY TPB

DATE 5/80

SCALE 21-06-79 108



GORDON E. AINSWORTH
& ASSOCIATES, INC.
20 Sugarloaf Street
SOUTH DEERFIELD, MASSACHUSETTS 01373
(413) 665-2161

JOB SUCKER BROOK DAM

SHEET NO. _____

OF _____



CALCULATED BY CLV

DATE 2/1/80

CHECKED BY CLV

DATE 5/80

SCALE 21-06-79/08



G. E. Ainsworth Associates
 20 Sugarloaf Street
 S. DEERFIELD, MA 01373
 Phone 665-2161

JOB SUCKER BROOK DAM


SHEET NO. _____ OF _____

CALCULATED BY CLV DATE 2/1/80

CHECKED BY gpe DATE 5/80

SCALE 21-06-79108

SCALE: HOR. = 1" = 1600'
 VERT. = 1" = 200'



V7 0 700 0 470 80 460 180 640 100 640

V7 240 460 250 680 260 700

K1 CHANNEL ROUTING STA 85+00

V1 1 1

V6 .04 .03 .04 598 637 600 .084

V7 0 621 1400 621 1500 600 1505 598 1510 598

V7 1420 100 2100 400 2150 621

V1 1 1

K1 CHANNEL ROUTING STA 93+00

V1 1 1

V6 .04 .03 .04 578 597 580 .025

V7 0 600 25 590 50 580 60 578 90 578

V7 100 580 450 580 950 600

K 99

A

A

A

A

A

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

| | | | RATIOS APPLIED TO FLOWS | |
|---------------|---------|---------|-------------------------|-------|
| OPERATION | STATION | AREA | PLAN RATIO | 1 |
| | | | | 1.00 |
| HYDROGRAPH AT | SA-5 | 0.00 | 1 | 4182. |
| | | (0.01) | (118.41) | (|
| ROUTED TO | RESC | 0.00 | 1 | 4182. |
| | | (0.01) | (118.41) | (|
| ROUTED TO | 3+00 | 0.00 | 1 | 4182. |
| | | (0.01) | (118.41) | (|
| ROUTED TO | 26+00 | 0.00 | 1 | 4182. |
| | | (0.01) | (118.41) | (|
| ROUTED TO | 56+00 | 0.00 | 1 | 4182. |
| | | (0.01) | (118.41) | (|
| ROUTED TO | 72+00 | 0.00 | 1 | 4182. |
| | | (0.01) | (118.41) | (|
| ROUTED TO | 87+00 | 0.00 | 1 | 4182. |
| | | (0.01) | (118.41) | (|
| ROUTED TO | 85+00 | 0.00 | 1 | 4182. |
| | | (0.01) | (118.41) | (|
| ROUTED TO | 53+00 | 0.00 | 1 | 4182. |
| | | (0.01) | (118.41) | (|

12. "Hydraulic Design of Spillways", EM 1110-2-1603, U.S. Army Corps of Engineers, 31 March 1965.
13. "Standard Project Flood Determinations", EM 1110-2-1411, U.S. Army Corps of Engineers, 26 March 1952.
14. "Hydrologic and Hydraulic Assessment", Appendix D of EC 1110-2-188, U.S. Army Corps of Engineers, 30 December 1977.
15. "Reviews of Spillway Adequacy, National Program of Inspection of Non-Federal Dams", ETL 1110-2-234, U.S. Army Corps of Engineers, 10 May 1978.
16. Hammer, Mark J., Water and Waste-Water Technology, John Wiley & Sons, Inc., New York, 1975.
17. "Hydraulic Charts For the Selection of Highway Culverts", Hydraulic Engineering Circular No. 5, U.S. Department of Commerce, Bureau of Public Roads, December 1965.
18. 33 CFR Part 22, Final Rule, "Engineering and Design; National Program For Inspection of Non-Federal Dams", ER 1110-2-106, U.S. Army Corps of Engineers, March 24, 1980.
19. "Water Resources Data For New Hampshire and Vermont - Water Year 1977", USGS Water-Data Report NH-VT-77-1, U.S. Geological Survey, Boston, Ma., 1978.
20. "Climatological Data - May 1979 - New England", Volume 91, No. 5, National Oceanic and Atmospheric Administration, National Climatic Center, Asheville, North Carolina.
21. "Climatological Data - Annual Summary - New England", Volume 90, No. 13, National Oceanic and Atmospheric Administration, National Climatic Center, Asheville, North Carolina.

REFERENCES

This is a general list of references pertinent to dam safety investigations. Not all references listed have necessarily been used in this specific report.

1. "Recommended Guidelines For Safety Inspection of Dams", Appendix D of ER 1110-2-106, Dept. of the Army, Office of the Chief of Engineers, Washington, D.C., 26 September 1979.
2. "HEC-1 Flood Hydrograph Package, Users Manual", The Hydrologic Engineering Center, U.S. Army Corps of Engineers, January 1973.
3. "Flood Hydrograph Package (HEC-1), Users Manual for Dam Safety Investigations", The Hydrologic Engineering Center, U.S. Army Corps of Engineers, September 1978.
4. HMR 33, "Seasonal Variations of Probable Maximum Precipitation, East of the 105th Meridian for Areas 10 to 1000 Square Miles and Durations from 6 to 48 Hours," U.S. Department of Commerce, NOAA, National Weather Service, 1956.
5. HMR 51, "All-Season Probable Maximum Precipitation, U.S. East of 105th Meridian for Areas from 1000 to 20,000 Square Miles and Durations from 6 to 72 Hours", U.S. Department of Commerce, NOAA, National Weather Service, 1974.
6. HYDRO-35, "Five-to-60 Minute Precipitation Frequency for the Eastern and Central United States", U.S. Department of Commerce, NOAA, National Weather Service, June 1977.
7. "Technical Paper No. 40, Rainfall Frequency Atlas of the United States", U.S. Department of Commerce, Weather Bureau, 1961.
8. Design of Small Dams, United States Department of the Interior, Bureau of Reclamation, Second Edition, 1973.
9. King, Horace W. and Brater, Ernest F., Handbook of Hydraulics, fifth edition, McGraw-Hill Book Co., Inc., New York, 1963.
10. "Flood Hydrograph Analyses and Computations", EM 1110-2-1405, U.S. Army Corps of Engineers, 31 August 1959.
11. "Technical Release No. 55, Urban Hydrology for Small Watersheds", U.S. Department of Agriculture, Soil Conservation Service (Engineering Division), January 1975.

APPENDIX F

REFERENCES

INFORMATION AS CONTAINED IN
THE NATIONAL INVENTORY OF DAMS

THIS SHEET TO BE FURNISHED BY
THE CORPS OF ENGINEERS

APPENDIX E

INFORMATION AS CONTAINED IN

THE NATIONAL INVENTORY OF DAMS

CONTENTS OF DAM SAFETY ANALYSIS

PLAN 1 INITIAL VALUE. SPILLWAY CREST TOP OF DAM
 1311.20 1302.00 1311.20
 54. 21. 54.
 CUREFLOW AIR2. 0. 4182.

| RATIO | MAXIMUM | MINIMUM | MAXIMUM | MINIMUM | CURATION | TIME OF | TIME OF |
|-------|-----------|----------|---------|---------|----------|-------------|---------|
| OF | RESERVOIR | DEPTH | STORAGE | OUTFLOW | OVER TOP | MAX OUTFLOW | FAILURE |
| PMF | W.S. LEV | OVER DAM | AC-FT | CFS | HOURS | HOURS | HOURS |
| 1.00 | 1311.16 | 0.06 | 54. | 27579. | 0.00 | 0.02 | 0.00 |

PLAN 1 STATION 26+00

| RATIO | MAXIMUM | MINIMUM | MAXIMUM | MINIMUM | TIME |
|-------|-----------|----------|---------|---------|-------|
| OF | RESERVOIR | DEPTH | STORAGE | OUTFLOW | TIME |
| PMF | W.S. LEV | OVER DAM | AC-FT | CFS | HOURS |
| 1.00 | 1311.16 | 0.06 | 54. | 27579. | 0.00 |

PLAN 1 STATION 56+00

| RATIO | MAXIMUM | MINIMUM | MAXIMUM | MINIMUM | TIME |
|-------|-----------|----------|---------|---------|-------|
| OF | RESERVOIR | DEPTH | STORAGE | OUTFLOW | TIME |
| PMF | W.S. LEV | OVER DAM | AC-FT | CFS | HOURS |
| 1.00 | 1311.16 | 0.06 | 54. | 27579. | 0.00 |

PLAN 1 STATION 72+00

| RATIO | MAXIMUM | MINIMUM | MAXIMUM | MINIMUM | TIME |
|-------|-----------|----------|---------|---------|-------|
| OF | RESERVOIR | DEPTH | STORAGE | OUTFLOW | TIME |
| PMF | W.S. LEV | OVER DAM | AC-FT | CFS | HOURS |
| 1.00 | 1311.16 | 0.06 | 54. | 27579. | 0.00 |

PLAN 1 STATION 80+00

| RATIO | MAXIMUM | MINIMUM | MAXIMUM | MINIMUM | TIME |
|-------|-----------|----------|---------|---------|-------|
| OF | RESERVOIR | DEPTH | STORAGE | OUTFLOW | TIME |
| PMF | W.S. LEV | OVER DAM | AC-FT | CFS | HOURS |
| 1.00 | 1311.16 | 0.06 | 54. | 27579. | 0.00 |

PLAN 1 STATION 85+00

| RATIO | MAXIMUM | MINIMUM | MAXIMUM | MINIMUM | TIME |
|-------|-----------|----------|---------|---------|-------|
| OF | RESERVOIR | DEPTH | STORAGE | OUTFLOW | TIME |
| PMF | W.S. LEV | OVER DAM | AC-FT | CFS | HOURS |
| 1.00 | 1311.16 | 0.06 | 54. | 27579. | 0.00 |

PLAN 1 STATION 93+00

| RATIO | MAXIMUM | MINIMUM | MAXIMUM | MINIMUM | TIME |
|-------|-----------|----------|---------|---------|-------|
| OF | RESERVOIR | DEPTH | STORAGE | OUTFLOW | TIME |
| PMF | W.S. LEV | OVER DAM | AC-FT | CFS | HOURS |
| 1.00 | 1311.16 | 0.06 | 54. | 27579. | 0.00 |

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

| RATIOS APPLIED TO FLOWS | | | |
|-------------------------|---------|---------|------------|
| OPERATION | STATION | AREA | PLAN RATIO |
| | | | 1.00 |
| HYDROGRAPH AT SA-5 | | | |
| | | 0.00 | 1 |
| | | (0.01) | (0.00) |
| ROUTED TO RES2 | | | |
| | | 0.00 | 1 |
| | | (0.01) | (0.00) |
| ROUTED TO 26+00 | | | |
| | | 0.00 | 1 |
| | | (0.01) | (0.00) |
| ROUTED TO 56+00 | | | |
| | | 0.00 | 1 |
| | | (0.01) | (0.00) |
| ROUTED TO 72+00 | | | |
| | | 0.00 | 1 |
| | | (0.01) | (0.00) |
| ROUTED TO 80+00 | | | |
| | | 0.00 | 1 |
| | | (0.01) | (0.00) |
| ROUTED TO 85+00 | | | |
| | | 0.00 | 1 |
| | | (0.01) | (0.00) |
| ROUTED TO 93+00 | | | |
| | | 0.00 | 1 |
| | | (0.01) | (0.00) |

STATION RES2

| TIME
(MRS) | (C) INTERPOLATED BREACH HYDROGRAPH
(D) COMPUTED BREACH HYDROGRAPH | | | | | | | | | | (*) POINTS AT NORMAL TIME INTERVAL | | | | |
|---------------|--|-------|-------|--------|--------|--------|--------|--------|--------|--------|------------------------------------|--|--|--|--|
| | 4000. | 6000. | 8000. | 10000. | 12000. | 14000. | 16000. | 18000. | 20000. | 22000. | C. | | | | |
| 0.00 1. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.00 2. | 0 | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.00 3. | 0 | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.00 4. | . | P | . | . | . | . | . | . | . | . | . | | | | |
| 0.00 5. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.00 6. | 0 | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.00 7. | 0 | R | . | . | . | . | . | . | . | . | . | | | | |
| 0.00 8. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.00 9. | . | C | . | . | . | . | . | . | . | . | . | | | | |
| 0.00 10. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.00 11. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 12. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 13. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 14. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 15. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 16. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 17. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 18. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 19. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 20. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 21. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 22. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 23. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 24. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 25. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 26. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 27. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 28. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 29. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 30. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 31. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 32. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 33. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 34. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 35. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 36. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 37. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 38. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 39. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 40. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 41. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 42. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 43. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 44. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 45. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 46. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 47. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 48. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 49. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 50. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 51. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 52. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 53. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 54. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 55. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 56. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 57. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 58. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.01 59. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.02 0. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.02 1. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.02 2. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.02 3. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.02 4. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.02 5. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.02 6. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.02 7. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.02 8. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.02 9. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.02 10. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.02 11. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.02 12. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.02 13. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.02 14. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.02 15. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.02 16. | . | . | . | . | . | . | . | . | . | . | . | | | | |
| 0.02 17. | . | . | . | . | . | . | . | . | . | . | . | | | | |

| TIME
(HOURS) | EIGHTH
OF PREACH
(HOURS) | PREACH
HYDROGRAPH
(CFS) | INTEGRALED
PREACH
(CFS) | = | | ACCUMULATED
ERROR
(CFS) | ACCUMULATED
ERROR
(AC-FT) |
|-----------------|--------------------------------|-------------------------------|-------------------------------|--------|--------|-------------------------------|---------------------------------|
| | | | | ERROR | ERROR | | |
| 0.000 | 0.000 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| 0.001 | 0.000 | 605. | 4265. | -3661. | -3.661 | -3.661 | -0.00 |
| 0.001 | 0.001 | 1205. | 4442. | -1933. | -1.933 | -5.594 | -0.00 |
| 0.001 | 0.001 | 1815. | 4718. | -2806. | -2.806 | -8.400 | -0.00 |
| 0.002 | 0.002 | 2415. | 4841. | -2449. | -2.449 | -10.849 | -0.00 |
| 0.002 | 0.002 | 3024. | 5232. | -5232. | -5.232 | -16.081 | -1.00 |
| 0.003 | 0.003 | 3628. | 5640. | -2012. | -2.012 | -18.093 | -1.00 |
| 0.003 | 0.003 | 4233. | 6255. | -1705. | -1.705 | -19.798 | -1.00 |
| 0.004 | 0.004 | 4836. | 6841. | -1604. | -1.604 | -21.402 | -1.00 |
| 0.004 | 0.004 | 5442. | 7331. | -1394. | -1.394 | -22.796 | -1.00 |
| 0.005 | 0.005 | 6047. | 7714. | -1162. | -1.162 | -23.957 | -1.00 |
| 0.005 | 0.005 | 6652. | 8077. | -1055. | -1.055 | -25.012 | -1.00 |
| 0.006 | 0.006 | 7257. | 8416. | -854. | -0.854 | -25.866 | -1.00 |
| 0.006 | 0.006 | 7861. | 8731. | -771. | -0.771 | -26.637 | -1.00 |
| 0.006 | 0.006 | 8466. | 9031. | -677. | -0.677 | -27.314 | -1.00 |
| 0.007 | 0.007 | 9071. | 9270. | -575. | -0.575 | -27.889 | -1.00 |
| 0.007 | 0.007 | 9676. | 9442. | -473. | -0.473 | -28.362 | -1.00 |
| 0.008 | 0.008 | 10280. | 10653. | -372. | -0.372 | -28.734 | -1.00 |
| 0.008 | 0.008 | 10885. | 11521. | -268. | -0.268 | -29.002 | -1.00 |
| 0.009 | 0.009 | 11490. | 12007. | -165. | -0.165 | -29.167 | -1.00 |
| 0.009 | 0.009 | 12094. | 12463. | -62. | -0.062 | -29.229 | -1.00 |
| 0.010 | 0.010 | 12699. | 12842. | 54. | 0.054 | -29.175 | -1.00 |
| 0.010 | 0.010 | 13304. | 13221. | 152. | 0.152 | -28.999 | -1.00 |
| 0.011 | 0.011 | 13908. | 14004. | 249. | 0.249 | -28.750 | -1.00 |
| 0.011 | 0.011 | 14513. | 14682. | 346. | 0.346 | -28.404 | -1.00 |
| 0.012 | 0.012 | 15118. | 15272. | 443. | 0.443 | -27.961 | -1.00 |
| 0.012 | 0.012 | 15722. | 16152. | 540. | 0.540 | -27.421 | -1.00 |
| 0.012 | 0.012 | 16327. | 16744. | 637. | 0.637 | -26.784 | -1.00 |
| 0.013 | 0.013 | 16932. | 17314. | 734. | 0.734 | -26.050 | -1.00 |
| 0.013 | 0.013 | 17537. | 17859. | 832. | 0.832 | -25.218 | -1.00 |
| 0.014 | 0.014 | 18141. | 18458. | 929. | 0.929 | -24.289 | -1.00 |
| 0.014 | 0.014 | 18746. | 19021. | 1026. | 1.026 | -23.263 | -1.00 |
| 0.015 | 0.015 | 19351. | 19575. | 1123. | 1.123 | -22.140 | -1.00 |
| 0.015 | 0.015 | 19956. | 20141. | 1220. | 1.220 | -20.920 | -1.00 |
| 0.016 | 0.016 | 20560. | 20694. | 1317. | 1.317 | -19.603 | -1.00 |
| 0.016 | 0.016 | 21165. | 21165. | 1414. | 1.414 | -18.189 | -1.00 |
| 0.017 | 0.017 | 21770. | 21770. | 1511. | 1.511 | -16.678 | -1.00 |
| 0.017 | 0.017 | 22375. | 21770. | 1608. | 1.608 | -15.070 | -1.00 |

| | | | | | | | | | |
|----|------|-------|------|-----|------|-----|------|-----|------|
| Y6 | .04 | .03 | .04 | 598 | 617 | 500 | .084 | | |
| Y7 | 0 | 621 | 1300 | 620 | 1500 | 400 | 1505 | 598 | 1510 |
| Y7 | 1520 | 600 | 2050 | 700 | 2150 | 621 | | | |
| K | 1 | 92.00 | | | | 1 | | | 1 |

K1 CHANNEL ROUTING STA 92+00

| | | | | | | | | | |
|----|-----|-----|-----|-----|-----|-----|------|-----|----|
| Y1 | 1 | | | 1 | | | | | |
| Y6 | .04 | .03 | .04 | 578 | 597 | 800 | .025 | | |
| Y7 | 0 | 600 | 25 | 590 | 50 | 580 | 60 | 578 | 90 |
| Y7 | 1.0 | 500 | 500 | 500 | 500 | 600 | | | |

95

A
A
A
A
A

[illegible]

A BRICK AT TOP OF DAM

15

1.3

RI SUBAREA 3 FC: 011 C

1

107

2534 I K

| | | | |
|----|------|------|------|
| Y9 | 1308 | 1209 | 1210 |
|----|------|------|------|

| | | |
|-------|-------|----|
| 20-76 | 81-42 | 54 |
| 21-76 | 82 | 55 |

21

| | | | |
|-----|-----|-----|------|
| \$3 | 109 | 1.5 | 1289 |
|-----|-----|-----|------|

215 9W113D 7311743 1X

| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|-----|
| 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 | 32 | 33 | 34 | 35 | 36 | 37 | 38 | 39 | 40 | 41 | 42 | 43 | 44 | 45 | 46 | 47 | 48 | 49 | 50 | 51 | 52 | 53 | 54 | 55 | 56 | 57 | 58 | 59 | 60 | 61 | 62 | 63 | 64 | 65 | 66 | 67 | 68 | 69 | 70 | 71 | 72 | 73 | 74 | 75 | 76 | 77 | 78 | 79 | 80 | 81 | 82 | 83 | 84 | 85 | 86 | 87 | 88 | 89 | 90 | 91 | 92 | 93 | 94 | 95 | 96 | 97 | 98 | 99 | 100 |
|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|-----|

| | | | |
|----|-----|------|-----|
| Y7 | 200 | 1140 | 270 |
|----|-----|------|-----|

AL CHANNEL FIGHTING STAFF

100

| | | | |
|----|-----|-----|----|
| 47 | 435 | 200 | 50 |
|----|-----|-----|----|

K1 CHANNEL ROUTING STA

| | | | |
|----|---|----|---|
| VI | 1 | 03 | 0 |
|----|---|----|---|

| | | | |
|----|-----|-----|----|
| 31 | 624 | 911 | 24 |
|----|-----|-----|----|

WISCONSIN TROOPERS IN

| | | | | |
|--|----|---|---|---|
| | yl | l | c | f |
|--|----|---|---|---|

| | | | |
|----|----|-----|----|
| 11 | 3 | 100 | 25 |
| 17 | 24 | 160 | 25 |

AL GAIL RUTHE STA

VI I

10

D-37

GORDON E. AINSWORTH
& ASSOCIATES, INC.
20 Sugarloaf Street
SOUTH DEERFIELD, MA 01373
Phone 665-2161

JOB SUCKER BROOK DAM

SHEET NO. _____

OF _____

CALCULATED BY QPD

DATE 9/16/80


CHECKED BY QPD

DATE 9/16/80

SCALE n/a

BREACH CRITERIA

EARTH DAM, NO CORE WALL



RULE OF THUMB FOR SUDDEN BREACH

SUDDEN BREACH

$$Q = \frac{8}{27} W_b \sqrt{g} Y_o^5$$

$$W_b = 100' \quad Y_o = 27.2'$$

$$Q = 23,900 \text{ cfs} \pm$$

ADDITIONAL FLOOD PROTECTION FROM SPILLWAY

$$\text{TOTAL FLOOD AT TLD} = 4280 \text{ cfs} \pm$$

$$\text{LESS DIVERSION FLOW TO POND} = 100 \text{ cfs} \pm$$

$$4180 \text{ cfs}$$

TOTAL PEAK OUTFLOW FROM DAM

$$Q_p = 23,900 \text{ cfs} + 4180 \text{ cfs} = 28,080 \text{ cfs} \approx 28,000 \text{ cfs}$$

HEC-1 DB BREACH PROGRAM

CALCULATION INTERVAL = 1 MINUTE

BREACH TIME

PEAK OUTFLOW (cfs)

0.03 hr.

24,100

0.02

30,200

0.025

26,800

USE 0.023 hr. = 1.38 min

28,000 cfs

COMPANY OF DA SAFETY ANALYSIS

PLAN 1

INITIAL VALUE SPILLWAY CREST TOP OF DAM
1311.20 1302.00 1311.20
54. 21. 54.
4182. 0. 4182.

ELEVATION
STORAGE
OUTFLOW

RATIO MAXIMUM MAXIMUM MAXIMUM DURATION TIME OF TIME OF
OF RESERVOIR STORAGE CFS CVER TOP MAX OUTFLOW FAILURE
PWF W.S.FLEV OVER DAM AC-FT HOURS HOURS HOURS
1.00 1311.20 0.00 54. 4182. 0.17 0.00 0.00

PLAN 1 STATION 3+00

RATIO MAXIMUM MAXIMUM MAXIMUM TIME
FLOW.CFS STAGE.FT HOURS
1.00 4182. 1261.3 0.02

PLAN 1 STATION 26+00

RATIO MAXIMUM MAXIMUM MAXIMUM TIME
FLOW.CFS STAGE.FT HOURS
1.00 4182. 1125.3 0.02

PLAN 1 STATION 56+00

RATIO MAXIMUM MAXIMUM MAXIMUM TIME
FLOW.CFS STAGE.FT HOURS
1.00 4182. 808.0 0.02

PLAN 1 STATION 72+00

RATIO MAXIMUM MAXIMUM MAXIMUM TIME
FLOW.CFS STAGE.FT HOURS
1.00 4182. 808.3 0.02

PLAN 1 STATION 80+00

RATIO MAXIMUM MAXIMUM MAXIMUM TIME
FLOW.CFS STAGE.FT HOURS
1.00 4182. 644.1 0.02

PLAN 1 STATION 85+00

RATIO MAXIMUM MAXIMUM MAXIMUM TIME
FLOW.CFS STAGE.FT HOURS
1.00 4182. 600.6 0.02

PLAN 1 STATION 93+00

RATIO MAXIMUM MAXIMUM MAXIMUM TIME
FLOW.CFS STAGE.FT HOURS
1.00 4182. 580.5 0.02

END

FILMED

8-85

DTIC